STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET

CURB

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	REMARKS
ITEM 900.640 SPECIAL PROVISION (VERTICAL GRANITE CURB, MOUNTABLE)				
2+17	1+70	45.1		R=340
1+70	1+70	49.8		R=28
1+40	1+50	38.9		STRAIGHT
	SUBTOTAL =	133.8		
	ROUNDING =	1.2		
	ITEM TOTAL =	135.0		

GUARD RAIL

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	END TREATMENT BEGIN EA	END TREATMENT END EA
ITEM 621.75 REMOVE AND RESET GUARDRAIL					
14+81.25	18+39.42		387.5		ANCHOR
100+21.40	100+90.00	114.3			
	SUBTOTAL =	501.8			
	ROUNDING =	3.2			
	ITEM TOTAL =	505.0			
ITEM 621.20 STEEL BEAM GUARDRAIL, GALVANIZED					
ESTIMATED QUANTITY TO ACCOUNT FOR ANY DAMAGE DURING REMOVAL AND RESETTING OF EXISTING GUARDRAIL					
	ITEM TOTAL =	50.0	EST		

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA. IN	LENGTH FT	TRENCH EARTH CY	TRENCH ROCK CY	GRAN BKFILL CY	FB EA	MKR PST EA
ITEM 605.21 8 INCH UNDERDRAIN CARRIER PIPE										
16+89.42	17+00.15	U	RT	8	11	-	-	-	-	-
	SUBTOTAL =	11								
	ROUNDING =	1								
	ITEM TOTAL =	12								

McFarland Johnson

PROJECT NAME: MORRISTOWN
PROJECT NUMBER: STPG SGNL(47)

FILE NAME: z15t047idt.dgn
PROJECT LEADER: J. SANTACRUCE
DESIGNED BY: R. LUCHINI
ITEM DETAIL SHEET

PLOT DATE: 5/13/2016
DRAWN BY: R. LUCHINI
CHECKED BY: B. COLBURN
SHEET 18 OF 58