



ID NUMBER	SIGN TEXT	SIZE OF SIGN		NUMBER OF SIGNS REQ'D	AREA OF EACH SIGN (SF)	COLOR	REMARKS
		WIDTH (IN)	HEIGHT (IN)				
W20-2	DETOUR AHEAD	48	48	5	16.0	BLACK AND FLOURESCENT ORANGE	INSTALL ON 2 POSTS
W20-3	ROAD CLOSED 0.7 MILES AHEAD	48	48	1	16.0	BLACK AND FLOURESCENT ORANGE	INSTALL ON 2 POSTS
M1-5	VT 100	30	24	8	5.0	GREEN AND WHITE	
M1-5	VT 15A	30	24	4	5.0	GREEN AND WHITE	
M1-5	VT 12	30	24	4	5.0	GREEN AND WHITE	
M3-1	NORTH	24	12	4	2.0	GREEN AND WHITE	MOUNT BELOW M4-8
M3-3	SOUTH	24	12	1	2.0	GREEN AND WHITE	MOUNT BELOW M4-8
M4-8	DETOUR	24	12	8	2.0	BLACK AND FLOURESCENT ORANGE	MOUNT ABOVE M1-5
M4-8a	END DETOUR	24	18	3	3.0	BLACK AND FLOURESCENT ORANGE	
M4-5	TO	24	12	4	2.0	GREEN AND WHITE	MOUNT ABOVE M1-5
M6-3	↑	21	15	5	2.19	BLACK AND FLOURESCENT ORANGE	MOUNT BELOW M1-5
M6-1L	←	21	15	2	2.19	BLACK AND FLOURESCENT ORANGE	MOUNT BELOW M1-5
M6-1R	→	21	15	3	2.19	BLACK AND FLOURESCENT ORANGE	MOUNT BELOW M1-5
R11-3B	ROAD CLOSED 0.7 MILES AHEAD	30	60	1	12.5	BLACK AND FLOURESCENT ORANGE	INSTALL ON 2 POSTS

THE ESTIMATED QUANTITIES OF "PERMANENT CONTROLS" ARE HEREBY LISTED. ADDITIONAL SIGNS REQUIRED FOR THE CONSTRUCTION APPROACHES ARE SHOWN ON STANDARD DETAIL T-10. THE CONTRACTOR IS RESPONSIBLE FOR ALL "OPERATIONAL CONTROLS" REQUIRED UNDER SECTION 641 OF THE 2011 VTRANS SPECIFICATIONS AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), PART VI LATEST EDITION.

PROJECT NAME: MORRISTOWN  
PROJECT NUMBER: STPG SGNL(47)  
FILE NAME: z15t047detour.dgn  
PROJECT LEADER: J. SANTACRUCE  
DESIGNED BY: J. SANTACRUCE  
DETOUR PLAN  
PLOT DATE: 5/13/2016  
DRAWN BY: J. SANTACRUCE  
CHECKED BY: B. COLBURN  
SHEET 58 OF 58

