

Installation Options

- Cabinet Rail Mount
 - Slots support most cabinet rail spacing's
 - Rail lugs available separately
- DIN Rail Mount
 - DIN rail available separately

General Data

- Electrical
 - 110 or 220 VAC, 50 or 60 Hz, 30W
 - Ground wire to cabinet ground
- Interfaces
 - 4x 5-pin Phoenix connectors to radar units
 - 4x RJ12 connectors to TMLB cabinet interface
(order appropriate number cables with panel)
- Indicators
 - Power Status LEDs on panel and power supply
- Environmental
 - -34°C to +74°C (-29°F to +165°F)
 - 0 to 95% relative humidity, non-condensing
- Regulatory:
 - NEMA TS 2-2003 compliant
 - TEES
 - FCC Part 15, Class A
- Product support and training available through the EGI Learning Center

Basic Specifications

- Dimensions & Weight (Cabinet Rail Mount):
 - W x L x H: 241 mm x 160mm x 71 mm (9.5in x 6.3in x 2.8in)
 - Weight 0.8 kg (1.8 lb.)
- Dimensions & Weight (DIN Rail Mount):
 - W x L x H: 185mm x 127mm x 67mm (7.3in x 5in x 2.6in)
 - Weight 0.7 kg (1.5 lb.)
- Warranty
 - 2 years

ECONOLITE

3360 E La Palma Avenue, Anaheim, CA 92806 · 714-630-3700 · sales@econolite.com · www.econolite.com

3813860215-1

© 2015 Econolite Control Products, Inc. All rights reserved. Econolite Control Products, Inc. is an Econolite Group, Inc. company, certified to ISO 9001:2008, and reserves the right to change or update these specifications at any time without prior notification.

