



1-Way Assemblies

Designed to accommodate all traffic signals, with the exception of optically programmed. The Tallon Series Astro-Brac is designed to be tough and durable. It features all-axis adjustability and is designed to facilitate the mounting of any size signal to any size mast arm or pole.




APPROVED
By Erin Lewis at 4:51 pm, Jul 28, 2016



Astro-Brac Assy, Tallon Series, 1-Way Band Mount

Signal Section	Band Length	Coating
AB-0618 - <input type="text"/>	- <input type="text"/>	- <input type="text"/>
1=1 Sec	29=29" Band	PNC=Process No Color
2=2 Sec	36=36" Band	P__=Paint
3=3 Sec	42=42" Band	
4=4 Sec	48=48" Band	
5=5 Sec	56=56" Band	


Note:
Stainless steel upgrade available: includes stainless clamp screw and slotted washer.
Specify by including -SS in the part number, i.e., AB-0618-3-29-SS-PNC.



Astro-Brac Assy, Tallon Series, 1-Way Cable Mount

Signal Section	Cable Length	Coating
AB-0617 - <input type="text"/>	- <input type="text"/>	- <input type="text"/>
1=1 Sec	62=62" Cable	PNC=Process No Color
2=2 Sec	84=84" Cable	P__=Paint
3=3 Sec	96=96" Cable	
4=4 Sec		
5=5 Sec		

Note:
Stainless steel upgrade available: includes stainless cable and slotted washer.
Specify by including -SS in the part number, i.e., AB-0617-3-62-SS-PNC.




Astro-Brac Assy, Galaxy Series, 1-Way Cable Mount

Signal Section	Cable Length	Coating
AG-0125 - <input type="text"/>	- <input type="text"/>	- <input type="text"/>
1=1 Sec	62=62" Cable	PNC=Process No Color
2=2 Sec	84=84" Cable	P__=Paint
3=3 Sec	96=96" Cable	
4=4 Sec		
5=5 Sec		

Note:
Stainless steel upgrade available: includes stainless cable and slotted washer.
Specify by including -SS in the part number, i.e., AG-0125-3-62-SS-PNC.

- Note: 1. All assemblies are supplied standard with stainless steel fasteners.
2. See Reference Section for clamp kit pole diameters.
3. See Reference Section for available paint colors.



Astro-Brac

pelco
PELCO PRODUCTS, INC.