

Cluster Assemblies


The Atlas Large Capacity series of Astro-Brac can conceal one 3/4" diameter or two 5/8" diameter conduits. The cluster assemblies are designed to mount five-section heads to any size or shape of mast arm or pole.



APPROVED
By Erin Lewis at 5:10 pm, Jul 28, 2016


Astro-Brac

pelco
 PELCO PRODUCTS, INC.




Astro-Brac Assy, Atlas Series, 5-Sec Cluster, Articulated Serrated Cable Mount

AS-0162 - Cable Length - Coating
 62=62" Cable PNC=Process No Color
 84=84" Cable P_ =Paint
 96=96" Cable




Note:
Stainless steel upgrade available: includes stainless cable and slotted washer.
Specify by including -SS in the part number, i.e., AS-0162-62-SS-PNC.




Astro-Brac Assy, Atlas Series, 5-Sec Cluster, Articulated Serrated Tenon Mount

AS-0187 - Cable Length - Coating
 62=62" Cable PNC=Process No Color
 84=84" Cable P_ =Paint
 96=96" Cable




Note:
Stainless steel upgrade available: includes stainless cable and slotted washer.
Specify by including -SS in the part number, i.e., AS-0187-62-SS-PNC.



Astro-Brac Assy, Galaxy Series, 5-Sec Cluster, Cable Mount

AG-0138 - Cable Length - Coating
 84 - P-34 Black Finish
 62=62" Cable PNC=Process No Color
 84=84" Cable P_ =Paint
 96=96" Cable



Note:
Stainless steel upgrade available: includes stainless cable and slotted washer.
Specify by including -SS in the part number, i.e., AG-0138-62-SS-PNC.

- Note: 1. All assemblies are supplied standard with stainless steel fasteners.
 2. See Reference Section for clamp kit pole diameters.
 3. See Reference Section for available paint colors.