

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ROADWAY	RAILROAD	BRIDGE	FULL CE	ROADWAY (ALTERNATE A)	ROADWAY (ALTERNATE B)	ROADWAY (ALTERNATE C)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
				210						210		CY	UNCLASSIFIED EXCAVATION	203.17	5			
			19600							19600		LF	SHOULDER BERM REMOVAL	203.40	233			
				10						10		CY	TRENCH EXCAVATION OF EARTH	204.20	4			
			1							1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.			
				300						300		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	18			
			56600							56600		LF	MILLED RUMBLE STRIPS (CENTERLINE)	213.10	579			
				60						60		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25	-			
				30						30		CY	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.26	-			
			1							1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
			28590							28590		LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M324 (ASTM D 6890) TYPE II)	417.20	282			
				5						5		GAL	WATER REPELLENT, SILANE	514.10	-			
					260					260		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	9			
					100					100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.			
			36							36		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	EST.			
				240						240		LF	6 INCH UNDERDRAIN PIPE	605.10	6			
				20						20		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	3			
			270							270		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
			200							200		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
			100							100		HR	TRUCK RENTAL	608.37	EST.			
			1030							1030		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
			3800							3800		HR	FLAGGERS	630.15	EST.			
						1				1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
						1				1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
						3000				3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
			1							1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
			1							1		LS	TRAFFIC CONTROL	641.10	-			
			6							6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
													BEGIN OPTION AA					
			735							735		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482				
			735							735		LF	SPECIAL PROVISION (DURABLE 24 INCH STOP BAR, POLYUREA)(28 MILS)	900.640				
													END OPTION AA					
													BEGIN OPTION BB					
			395							395		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492				
			395							395		EACH	SPECIAL PROVISION (DURABLE LETTER OR SYMBOL, POLYUREA)(28 MILS)	900.620				
													END OPTION BB					
													BEGIN OPTION CC					
			5							5		EACH	DURABLE RAILROAD CROSSING SYMBOL, THERMOPLASTIC	646.512				
			5							5		EACH	SPECIAL PROVISION (DURABLE RAILROAD CROSSING SYMBOL, POLYUREA)(28 MILS)	900.620				
													END OPTION CC					

PROJECT NAME: MIDDLEBURY-FERRISBURGH  
 PROJECT NUMBER: NH SURF(55)  
 FILE NAME: p15v015.dgn PLOT DATE: 06-APR-2016  
 PROJECT LEADER: HARRINGTON DRAWN BY: BULLOCK  
 DESIGNED BY: BULLOCK CHECKED BY: HARRINGTON  
 QUANTITY SHEET 1 SHEET 6 OF 96