STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES / TOTALS / DESCRIPTIONS

										GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND
			480000							480000		SY	SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)	900.675	4678
													BEGIN OPTION DD		
			1700							1700		TON	SPECIAL PROVISION (AGGREGATE SHOULDERS)	900.680	
			1700							1700		TON	SPECIAL PROVISION (AGGREGATE SHOULDERS, RAP)	900.680	
													END OPTION DD		
				260						260		TON	SPECIAL PROVISION (BITIMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	13
			200							200		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.
				375						375		TON	SPECIAL PROVISION (RAILROAD BALLAST)	900.680	5
			200							200		CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	14
													BEGIN ALTERNATE ZA1		
							481000			481000		SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)(PG 70-28)(SBS POLYMER)(3/4" LIFT THICKNESS)	900.675	4590
													END ALTERNATE ZA1		
													BEGIN ALTERNATE ZA2		
								3270		3270		CWT	EMULSIFIED ASPHALT	404.65	110
								1		1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
								28100		28100		TON	SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(PG 70-28)(SBS POLYMER)(1" LIFT THICKNESS)	900.680	309
													END ALTERNATE ZA2		
													BEGIN ALTERNATE ZA3		
									1	1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
									28100	28100		TON	SPECIAL PROVISION (6.3 MM POLYMER-MODIFIED BITUMINOUS CONCRETE PAVEMENT)(PG 70-28)(SBS POLYMER)(1" LIFT THICKNESS)	900.680	309
									3270	3270		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	110
													END ALTERNATE ZA3		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)
460,710	SY	U.S. RTE. 7
8097	SY	VT. RTE. 22A
2393	SY	FERRISBURGH STATE HIGHWAY
900	SY	DRIVES
3222	SY	TOWN HIGHWAYS
4678	SY	RND.
480,000	SY	TOTAL
		ALTERNATE A
		SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT) (PG 70-28)(SBS POLYMER)(3/4" LIFT THICKNESS)
460,710	SY	U.S. RTE. 7
8,097	SY	VT. RTE. 22A
2,393	SY	FERRISBURGH STATE HIGHWAY
3,222	SY	TOWN HIGHWAYS
892	SY	PULLOUT IN NEW HAVEN MM 1.15
1,096	SY	PULLOUT IN FERRISBURGH MM 1.37
4,590	SY	RND.
481,000	SY	TOTAL
		ALTERNATE B & C
		SPECIAL PROVISION (6.3MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(PG 70-28)(SBS POLYMER)(1" LIFT THICKNESS)
26,875	TON	U.S. RTE. 7
472	TON	VT. RTE. 22A
140	TON	FERRISBURGH STATE HIGHWAY
188	TON	TOWN HIGHWAYS
52	TON	PULLOUT IN NEW HAVEN MM 1.15
64	TON	PULLOUT IN FERRISBURGH MM 1.37
309	TON	RND.
28,100	TON	TOTAL

PROJECT NAME: MIDDLEBURY-FERRISBURGH	
PROJECT NUMBER: NH SURF(55)	
FILE NAME: pl5v015.dgn	PLOT DATE: 12-APR-2016
PROJECT LEADER: HARRINGTON	DRAWN BY: BULLOCK
DESIGNED BY: BULLOCK	CHECKED BY: HARRINGTON
QUANTITY SHEET 3	SHEET 8 OF 96