


1-Way Assemblies

EAST COAST SIGNALS APPROVED FOR SUBMITTAL 11-4-16


Designed to accommodate all traffic signals, with the exception of optically programmed. The Tallon Series Astro-Brac is designed to be tough and durable. It features all-axis adjustability and is designed to facilitate the mounting of any size signal to any size mast arm or pole.



Astro-Brac Assy, Tallon Series, 1-Way Band Mount

Signal Section	Band Length	Coating
AB-0618 - <input type="text" value="4"/>	- <input type="text" value="42"/>	- <input type="text" value="P34"/>
1=1 Sec	See Note	PNC=Process No Color
2=2 Sec		P__=Paint
3=3 Sec		
4=4 Sec		
5=5 Sec		


Note:
Band Length: 29", 36", 42", 48", 56", 72", or 84".
Stainless steel upgrade available: includes stainless clamp screw and slotted washer.
Specify by including -SS in the part number, i.e., AB-0618-3-29-SS-PNC.



Astro-Brac Assy, Tallon Series, 1-Way Cable Mount

Signal Section	Cable Length	Coating
AB-0617 - <input type="text"/>	- <input type="text"/>	- <input type="text"/>
1=1 Sec	See Note	PNC=Process No Color
2=2 Sec		P__=Paint
3=3 Sec		
4=4 Sec		
5=5 Sec		

Note:
Cable Length: 62", 84", 96", 110", 120", 132", 144", or 220".
Stainless steel upgrade available: includes stainless cable and slotted washer.
Specify by including -SS in the part number, i.e., AB-0617-3-62-SS-PNC.



Astro-Brac Assy, Galaxy Series, 1-Way Cable Mount

Signal Section	Cable Length	Coating
AG-0125 - <input type="text"/>	- <input type="text"/>	- <input type="text"/>
1=1 Sec	See Note	PNC=Process No Color
2=2 Sec		P__=Paint
3=3 Sec		
4=4 Sec		
5=5 Sec		

Note:
Cable Length: 62", 84", 96", 110", 120", 132", 144", 220", or 280".
Stainless steel upgrade available: includes stainless cable and slotted washer.
Specify by including -SS in the part number, i.e., AG-0125-3-62-SS-PNC.

Note: 1. All assemblies are supplied standard with stainless steel fasteners.
2. See Reference Section page iv for cable and band clamp kit pole diameters.
3. See Reference Section for available paint colors.

