

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						352					352		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
						2					2		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50				
						2					2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						463					463		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						80					80		LF	TEMPORARY TRAFFIC BARRIER	621.90				
						2					2		EACH	ADJUST ELEVATION OF VALVE BOX	629.20				
						250					250		LF	DUCTILE IRON PIPE, CEMENT-LINED (8") (CL 52)	629.24				
						1					1		LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42				
						240					240		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						1200					1200		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							540				540		HR	EMPLOYEE TRAINEESHIP	634.10				
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1					1		LS	TRAFFIC CONTROL	641.10				
						1660					1660		LF	4 INCH WHITE LINE	646.20				
						1730					1730		LF	4 INCH YELLOW LINE	646.21				
						47					47		LF	24 INCH STOP BAR	646.26				
						8					8		EACH	LETTER OR SYMBOL	646.30				
						1190					1190		LF	TEMPORARY 4 INCH WHITE LINE	646.600				
						2550					2550		LF	TEMPORARY 4 INCH YELLOW LINE	646.610				
						910					910		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
						250			1670		1920		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								320			320		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								360			360		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								315			315		LB	SEED	651.15				
								2			2		LB	SEED, WINTER RYE	651.17				
								635			635		LB	FERTILIZER	651.18				
								3			3		TON	AGRICULTURAL LIMESTONE	651.20				
								3			3		TON	HAY MULCH	651.25				
						130					130		CY	TOPSOIL	651.35				
									65		65		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								170			170		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								390			390		SY	TEMPORARY EROSION MATTING	653.20				
								72			72		CY	VEHICLE TRACKING PAD	653.35				
								2			2		EACH	FILTER BAG	653.45				

PROJECT NAME: DUXBURY  
 PROJECT NUMBER: BF 013-4(47)  
 FILE NAME: z16b00lqty.dgn  
 PROJECT LEADER: J. OLUND  
 DESIGNED BY: B. TOOTHAKER  
 QUANTITY SHEET 2  
 PLOT DATE: 5/25/2016  
 DRAWN BY: S. MORGAN  
 CHECKED BY: D. MYERS  
 SHEET 7 OF 69

