

QUANTITY SHEET 3

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | TOTALS | | DESCRIPTIONS | | | | DETAILED SUMMARY OF QUANTITIES | | | |
|---------------------------------|--|--|--|--|--|---------|----------|-----------------|--------|-----------------|-------------|--------------|------|---|-------------|--------------------------------|------------|------|-------|
| | | | | | | ROADWAY | TRAINING | EROSION CONTROL | BRIDGE | FULL C.E. ITEMS | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | ROUND | QUANTITIES | UNIT | ITEMS |
| | | | | | | | | 960 | | | 960 | | LF | BARRIER FENCE | 653.50 | | | | |
| | | | | | | | | 620 | | | 620 | | LF | PROJECT DEMARCATION FENCE | 653.55 | | | | |
| | | | | | | | | 14 | | | 14 | | EACH | DECIDUOUS SEEDLINGS (ACER RUBRUM) (CONT.) (5') | 656.16 | | | | |
| | | | | | | | | 10 | | | 10 | | EACH | DECIDUOUS SEEDLINGS (QUERCUS BICOLOR) (CONT.) (5') | 656.16 | | | | |
| | | | | | | | | 24 | | | 24 | | EACH | DECIDUOUS SHRUBS (CORNUS AMOMUM) (CONT.) (30") | 656.35 | | | | |
| | | | | | | | | 72 | | | 72 | | EACH | DECIDUOUS SHRUBS (CORNUS SERICEA) (CONT.) (30") | 656.35 | | | | |
| | | | | | | | | 48 | | | 48 | | EACH | DECIDUOUS SHRUBS (VIRURNUM LENTAGO) (CONT.) (36") | 656.35 | | | | |
| | | | | | | | | 31 | | | 31 | | MGAL | LANDSCAPE WATERING | 656.65 | | | | |
| | | | | | | | | 130 | | | 130 | | CY | LANDSCAPE BACKFILL, TRUCK MEASUREMENT | 656.80 | | | | |
| | | | | | | 9 | | | | | 9 | | SF | TRAFFIC SIGNS, TYPE A | 675.20 | | | | |
| | | | | | | 16 | | | | | 16 | | LF | SQUARE TUBE SIGN POST AND ANCHOR | 675.341 | | | | |
| | | | | | | 8 | | | | | 8 | | EACH | REMOVING SIGNS | 675.50 | | | | |
| | | | | | | 4 | | | | | 4 | | EACH | ERECTING SALVAGED SIGNS | 675.60 | | | | |
| | | | | | | 3 | | | | | 3 | | EACH | SETTING SALVAGED POSTS | 675.61 | | | | |
| | | | | | | 2 | | | | | 2 | | EACH | DELINEATOR WITH STEEL POST | 676.10 | | | | |
| | | | | | | 25 | | | | | 25 | | LF | WIRED CONDUIT (1") (SCH80 PVC) | 678.23 | | | | |
| | | | | | | 1 | | | | | 1 | | EACH | JUNCTION BOX | 678.26 | | | | |
| | | | | | | 1 | | | | | 1 | | EACH | POWER DROP STANCHION, STREET LIGHTING | 679.55 | | | | |
| | | | | | | 1 | | | | | 1 | | LU | PRICE ADJUSTMENT, FUEL (N.A.B.I.) | 690.50 | | | | |
| | | | | | | | | | 730 | | 730 | | CY | SPECIAL PROVISION (STONE FILL, STREAM BED MATERIAL) (TYPE III) | 900.608 | | | | |
| | | | | | | | | | 10 | | 10 | | EACH | SPECIAL PROVISION (CPM SCHEDULE) | 900.620 | | | | |
| | | | | | | 1 | | | | | 1 | | EACH | SPECIAL PROVISION (RELOCATE FLASHING BEACON, GROUND MOUNTED) | 900.620 | | | | |
| | | | | | | | | | | | | | | BEGIN ALTERNATE C | | | | | |
| | | | | | | | | | 1 | | 1 | | LS | SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE) (FOOTINGS) | 900.645 | | | | |
| | | | | | | | | | 1 | | 1 | | LS | SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE) (PEDESTAL WALLS) | 900.645 | | | | |
| | | | | | | | | | | | | | | END ALTERNATE C | | | | | |
| | | | | | | | | | 1 | | 1 | | LS | SPECIAL PROVISION (REMOVAL OF TEMPORARY BRIDGE) | 900.645 | | | | |
| | | | | | | | | | 1 | | 1 | | LS | SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM) | 900.645 | | | | |
| | | | | | | 1 | | | | | 1 | | LU | SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.) | 900.650 | | | | |
| | | | | | | 1 | | | | | 1 | | LU | SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.) | 900.650 | | | | |
| | | | | | | 679 | | | | | 679 | | TON | SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY) | 900.680 | | | | |

PROJECT NAME: DUXBURY
 PROJECT NUMBER: BF 013-4(47)
 FILE NAME: z16b00lqty.dgn
 PROJECT LEADER: J. OLUND
 DESIGNED BY: B. TOOTHAKER
 QUANTITY SHEET 3
 PLOT DATE: 5/25/2016
 DRAWN BY: S. MORGAN
 CHECKED BY: D. MYERS
 SHEET 8 OF 69

