

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
								175			175		CY	TRENCH EXCAVATION OF EARTH	204.20	-			
								12			12		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
								990			990		LB	REINFORCING STEEL, LEVEL I	507.11	-			
								9			9		CY	CONCRETE, CLASS B	541.25	-			
								37			37		LF	18" RCP CLASS V	601.0817	-			
								45			45		LF	18" CPEP(SL)	601.2615	-			
								1			1		EACH	18" CPEPES	601.7015	-			
								2			2		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE (4' X 4')	604.18	-			
								3			3		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE (4' X 6')	604.18	-			
								2			2		MGAL	DUST CONTROL WITH WATER	609.10	-			
								1			1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	-			
								4			4		CY	STONE FILL, TYPE I	613.10	-			
								25			25		LF	REMOVE AND RESET GUARDRAIL	621.75	-			
								300			300		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-			
								1100			1100		HR	FLAGGERS	630.15	-			
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
								1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
								3			3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								9			9		SY	GEOTEXTILE UNDER STONE FILL	649.31	-			
									135		135		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515	-			
									20		20		LB	SEED	651.15	-			
									110		110		LB	FERTILIZER	651.18	-			
									0.5		0.5		TON	AGRICULTURAL LIMESTONE	651.20	-			
									0.5		0.5		TON	HAY MULCH	651.25	-			
									100		100		CY	TOPSOIL	651.35	-			
									1		1		LS	EPSC PLAN	652.10	-			
									40		40		HR	MONITORING EPSC PLAN	652.20	-			
									1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
									115		115		SY	TEMPORARY EROSION MATTING	653.20	-			
									30		30		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	-			
									20		20		CY	VEHICLE TRACKING PAD	653.35	-			
									1		1		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-			
									2		2		EACH	FILTER BAG	653.45	-			
									280		280		LF	BARRIER FENCE	653.50	-			
									240		240		LF	PROJECT DEMARCATION FENCE	653.55	-			
									3		3		EACH	SPECIAL PROVISION (INLET PROTECTION DEVICE, FILTER FIBER)	900.620	-			
								100			100		HR	SPECIAL PROVISION (HORIZONTAL DIRECTION DRILLING OBSTRUCTION REMOVAL)	900.630	-			
									40		40		HR	SPECIAL PROVISION (TRENCHLESS PIPE OBSTRUCTION REMOVAL)	900.630	-			
									54		54		LF	SPECIAL PROVISION (HORIZONTAL DIRECTIONAL DRILLING)(10")(HDPE)	900.640	-			

PROJECT NAME: EAST MONTPELIER
 PROJECT NUMBER: BF EWP2(1)
 FILE NAME: 06_Quantities - ER.dgn PLOT DATE: 6/14/2016
 PROJECT LEADER: T. KNIGHT DRAWN BY: C. GENDRON
 DESIGNED BY: K. RICHARDSON CHECKED BY: E. ALLING
 QUANTITY SHEET QS 1 SHEET 6 OF 42

