


# ERITECH®

- Features a single-use ceramic mold which eliminates the need for a mold and frame and / or handle clamps.
- Produces a permanent connection that will not loosen or corrode.
- Fits copper-bonded (threaded and plain), galvanized and stainless steel ground rods.
- Simple to use.
- NEC® compliant
- cULus® Listed
- Rural Utilities Service (RUS) accepted

## CADWELD® ONE SHOT

For Connections to Ground Rods



The CADWELD® ONE SHOT produces a permanent exothermically welded connection to a ground rod that will not loosen, corrode away, or increase in resistance for the life of the installation.


<b>Tran Systems</b>		Vermont Agency of Transportation Lyndon STPG SGNL(48) Project
<input checked="" type="checkbox"/>	Approved	Fabrication/Installation may be undertaken
<input type="checkbox"/>	Approved as Corrected	Approval provided comments are incorporated
<input type="checkbox"/>	Correct, Revise and Resubmit	Fabrication/Installation MAY NOT be undertaken
<input type="checkbox"/>	No Action Taken	
Review / approval does not relieve the contractor from complying with all the requirements of the contract		



Position CADWELD ONE SHOT and wire on prepared ground rod. Dump the welding material into the ceramic crucible.



Set the lid on the CADWELD ONE SHOT body and add the starting material.



Initiate the reaction with T320 flint ignitor



The reaction produces a finished permanent exothermic connection



# ERICO®