DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB CLARENDON VT ROUTE 7B							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	4.411	F	M3-3										1		X														
		F	VM1-5										1																
		F	M3-3	24	12		7/20/17	2.00								1		13'-3" X							SOUTH, GREEN ON WHITE	X		
		F	VM1-5	24	24			4.00																					E-136
SB	4.373	F	R2-1	24	30		7/20/17	5.00								1		12'-6" X							INSTALL 195' DOWNSTATION FROM EXIST. SIGN AT MP 4.411 SB	X		
SB	4.336	F	R2-1										1		X														
SB	3.716	F	R2-1				7/20/17						1	X															
		F	R2-1	24	30			5.00																			INSTALL SIGN ON RETAINED POST	X		
SB	3.586	F	W1-2L				LEFT CURVE						1		X														
		F	W13-1P				45 MPH						1																
SB	3.526	F	W1-2L	30	30		7/20/17	6.25								1		14'-0" X							INSTALL SIGN 315' DOWNSTATION FROM EXIST. SIGN AT MP 3.586 SB	X		
SB	3.415	F	VD-701				7/20/17						1		X														
		F	VD-701	6	10			0.42								1	8'-6" X												T-42
SB	3.191	F	W2-1				CROSS ROAD						1		X														
SB	3.071	FE	D3-1				PVT. CROWN POINT DR.						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	22.67	0.00	0	0	0	9	0	0	4		55.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	154.3	0.0	1	0	0	37	0	0	17		220.0		2	279.0							

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Clarendon7B SB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
CLARENDON VT-7B SB 1 SHEET **27** OF **264**