DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB LUDLOW VT ROUTE 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	1.333	A	W11-1				BICYCLE WARNING						1		X												**NOTE: BEGIN CLASS 1 TOWN HIGHWAY. STICKERS ON BACK OF SIGNS SHALL READ "LUDLOW", NOT "VAOT"**			
		A	W16-1P				SHARE THE ROAD 8/10/17						1																
		A	W11-1	30	30			6.25								1		13'-9" X								PROVIDE 7' MINIMUM CLEAR HEIGHT	X		
		A	W16-1P	18	24			3.00																			X		
NB	1.348	A	W11-2				PEDESTRIAN TRAFFIC						1	X															
		A	W7-3aP				NEXT 1 MILE 8/11/17						1																
		A	W11-2	30	30	FYG		6.25																		INSTALL ON RETAINED POST PROVIDE 7' MINIMUM CLEAR HEIGHT	X		
		A	W7-3aP	24	18	FYG	8/30/17	3.00																			X		
NB	1.363	A					8/11/17 NO PARKING ORDINANCE				1	1	1			1		12'-6" X								REMOVE AND SALVAGE SIGN ONTO NEW POST. PROVIDE 7' MINIMUM CLEAR HEIGHT			
NB	1.428	A					FLASHING BEACON			1				X													RETAIN FLASHING BEACON			
		A	W16-9P				AHEAD						1																
		A	S1-1				SCHOOL ADVANCE WARNING						1																
		A					RADAR SPEED DISPLAY SIGN																				TOWN TO MOVE TO SIGN ASSEMBLY AT MP 1.303 NB			
		A	R2-1				8/11/17 SPEED LIMIT 30																				TOWN TO REMOVE SIGN			
		A	S1-1	36	36	FYG	AHEAD 8/29/17	9.00																		INSTALL ON RETAINED POST	X		
							SHEET TOTALS	27.50	0.00	1	1	1	7	0	0	2		30.0		0	0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	754.3	0.0	42	13	13	190	0	0	65		945.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Ludlow103 NB.xls**
PROJECT MANAGER: **D. MUNRO**
DESIGNED BY: **P. MCKECHNIE**
LUDLOW VT-103 NB 7
PLOT DATE: **2/27/2017**
DRAWN BY: **W. GORDON**
CHECKED **BRZEZOWSK**
SHEET **39** OF **264**