DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB LUDLOW VT ROUTE 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	2.313	F	VR-921L	30	30		8/17/17	6.25								1		11'-6" X								INSTALL SIGN BEHIND SIDEWALK, 10' UPSTATION FROM UTILITY POLE IN FRONT OF SUNOCO GAS STATION. PROVIDE 7' MINIMUM CLEAR HEIGHT. INSTALL POST AND ANCHOR IN SLEEVE			E-145A
SB	2.308	G	R7-1				8/17/17						1		X												RETURN SIGN TO TOWN			
		G	R7-201										1														RETURN SIGN TO TOWN			
		G	R7-1	12	18			1.50								1		12'-6" X								NOTE: DOUBLE HEADED ARROW PROVIDE 7' MINIMUM CLEAR HEIGHT	X		
		G	R7-201	12	6			0.50																		INSTALL POST AND ANCHOR IN SLEEVE	X		
SB	2.293	F	VR-921L				LANE ASSIGNMENT						1		X															
		F	M2-1	21	15		8/17/17	2.19								1		14'-3" X								INSTALL POST IN PLACE OF EXISTING LANE ASSIGNMENT SIGN JCT, GREEN ON WHITE	X		
		F	VM5-1	30	24			5.00																		PROVIDE 7' MINIMUM CLEAR HEIGHT			E-136I
SB	2.283	G	R7-1				NO PARKING ANYTIME <--->						1		X												RETURN SIGN TO TOWN			
		G	R7-201				TOW AWAY ZONE PLAQUE						1														RETURN SIGN TO TOWN			
SB	2.274	H	R1-1				STOP			1				X															
		G	VD-700				MILE MARKER 1030/1410/0227			1																				
SB	2.273	F	W11-2				PEDESTRIAN TRAFFIC (SOLAR POWERED) (FLASHING LED)			1				X																
		F	W16-7pL				LEFT DIAGONAL ARROW PLAQUE			1																				
SIGN SUMMARY SHEET							SHEET TOTALS	15.44	0.00	4	0	0	5	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	502.1	0.0	48	5	5	120	0	0	62		870.0		2	217.0								

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Ludlow103 SB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
LUDLOW VT-103 SB 11 SHEET **72** OF **264**