

DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	SHSM	SIGN DETAILS SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
																	1.88	2.42	3.35		7.60	9.00	10.80			14.60			
NB MOUNT HOLLY VT ROUTE 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK							
NB	4.119	A	W10-3				8/23/17 Summit Rd TH-4 LEGAL LOAD LIMIT 24,000 POUNDS 8/17/17																						
NB	4.150	A	W10-3	36	36			9.00								2		15'-0" 14'-9" X						INSTALL ±165 FT. NORTH OF EXISTING SIGN AT MP 4.119 NB	X				
		A	W16-8p	24	8			1.33																INSTALL ON LEFT POST		5			
NB	4.230	C	VR-017											1	X									OLD TURNPIKE RD (TH-4)					
		C	VR-017	24	30		5.00																INSTALL ON RETAINED POST			T-70			
NB	4.230	AB	D3-1	68	12		Old Turnpike Rd TH-4 8/17/17	5.67								2		11'-6" 10'-9" X						INSTALL INDEPENDENTLY ON TWO POSTS ON LEGAL LOAD SIDE OF THE INTERSECTION		7			
NB	4.244	D					OLD TURNPIKE ROAD TH						1		X														
NB	4.244	D	R1-1				STOP																						
		C	VD-700				STOP 8/17/17 MILE MARKER 1030 / 1112 / 0425						1																
		D	R1-1	30	30			6.25							1		13'-6" X							X					
		C	VD-700				MILE MARKER 1030 / 1112 / 0425						1										INSTALL BACK TO BACK ON STOP SIGN POST						
NB	4.965	A	VD-062B				OFFICIAL BUSINESS DIRECTIONAL SIGN					1			X								Village Baptist Church						
SIGN SUMMARY SHEET							SHEET TOTALS	27.25	0.00	1	1	1	5	0	0	5		75.0		0	0.0	0.0	0.0	0.0	PROJECT NAME: STATEWIDE-SOUTH REGION	PROJECT NUMBER: STPG SIGN(57)			
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							VERMONT AGENCY OF TRANSPORTATION	TOWN DIRECTIONAL TOTALS	349.8	0.0	22	7	7	78	0	0	48		680.0		0		0.0						FILE NAME: z16t041Mt Hollv103 NB.xls
																							PROJECT MANAGER: D. MUNRO	DRAWN BY: W. GORDON					
																								DESIGNED BY: P. MCKECHNIE	CHECKED: BRZEZOWSKI				
																								MOUNT HOLLY VT-103 NB 6	SHEET 88 OF 264				