DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB MOUNT HOLLY VT 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	4.299	F	W10-3R				HIGHWAY-RAIL GRADE CROSSING ADVANCE WARNING 8/22/17						1		X			15'-3" 14'-9"											
		F	W10-3R	36	36			9.00								2		X									X		
		F	W16-8p	24	8			1.33																		INSTALL ON RIGHT POST		5	
SB	4.254	F					8/22/17						1	X																
		F		24	24			4.00																		INSTALL ON RETAINED POST		3	
SB	4.209	G	VR-017				8/15/17						1	X												SUMMIT RD (TH-42)			
		G	VR-017	24	30			5.00																		INSTALL ON RETAINED POST			T-70
SB	4.209	EF	D3-1	64	12		8/15/17	5.33								2		15'-3" 14'-9"								INSTALL INDEPENDENTLY ON TWO POSTS ON LEGAL LOAD SIDE OF THE INTERSECTION		7	
SB	4.194	H	R1-1				STOP						1		X														
		G	VD-700				MILE MARKER 1030 / 1112 / 0423				1		1																	
		H	R1-1	30	30		8/15/17	6.25								1		12'-9"									X		
		G	VD-700				MILE MARKER 1030 / 1112 / 0423					1														INSTALL BACK TO BACK ON STOP SIGN POST			
SB	4.193	EF	D3-1				SUMMIT ROAD 42						1		X														
SB	4.164	F					PARKING AREA ---> 8/22/17						1	X																
		F		24	18			3.00																		INSTALL ON RETAINED POST		3	
SIGN SUMMARY SHEET							SHEET TOTALS	33.92	0.00	0	1	1	7	0	0	5		75.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	367.7	0.0	11	4	5	82	0	0	41		585.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Mt Hollv103 SB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
MOUNT HOLLY VT-103 SB 7 SHEET **103** OF **264**