DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB WALLINGFORD VT RTE 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	1.235	F	W1-2L	30	30	FY	9/12/17	6.25								1		14'-6" X								INSTALL SIGN 400' DOWNSTATION FROM EXISTING SIGN AT MP 0.131 SB	X		
		F	W13-1P	18	18	FY	40 MPH 10/10/17	2.25																			X		
SB	1.191	F	R8-3				NO PARKING SYMBOL SYMBOL						1	X																
		F	M4-14				BEGIN PLAQUE						1																	
		G	R8-3	24	24		9/14/17	4.00																		INSTALL ON RETAINED POST	X		
		G	M4-14	24	12		BEGIN 4/9/18	2.00																		BEGIN, BLACK ON WHITE	X		
SB	1.183	F	W1-8L				LEFT CHEVRON						1		X														
		F	W1-8L	18	24	FY	9/13/17	3.00								1		12'-0" X									X		
SB	1.182	E	W1-8R				RIGHT CHEVRON						1		X														
		E	W1-8R	18	24	FY	9/13/17	3.00								1		12'-0" X									X		
SB	1.173	F	W1-8L				LEFT CHEVRON						1		X														
SB	1.173	E	W1-8R				RIGHT CHEVRON						1		X														
SB	1.168	F	W1-8L	18	24	FY	9/13/17	3.00								1		12'-9" X									X		
SB	1.167	E	W1-8R	18	24	FY	9/13/17	3.00								1		13'-0" X									X		
SB	1.164	F	W1-8L				LEFT CHEVRON						1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	26.50	0.00	0	0	0	7	0	0	5		75.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	163.5	0.0	7	0	0	40	0	0	21		305.0		0		0.0							

PROJECT NAME: STATEWIDE-SOUTH REGION
PROJECT NUMBER: STPG SIGN(57)
FILE NAME: z16t041Wallingford103 SB.xls PLOT DATE: 2/27/2017
PROJECT MANAGER: D. MUNRO DRAWN BY: W. GORDON
DESIGNED BY: P. MCKECHNIE CHECKED BRZEZOWSK
WALLINGFORD VT-103 SB 2 SHEET 117 OF 264