DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB VERNON VT ROUTE 142							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		A	W16-2P				1500 FEET						1																
		A	W12-2	36	36	FY	11/14/17	9.00								2		13'-9" X										X	
		A	W16-2P	30	24	FY	11/15/17	5.00																				X	
NB	0.855	A	W1-4L				LEFT REVERSE CURVE						1		X														
		A	W13-1P				35 MPH PLAQUE						1																
NB	0.960	A	W11-1				BICYCLE TRAFFIC						1		X														
		A	W16-1P				SHARE THE ROAD						1																
NB	1.005	A					SCHOOL BUS STOP AHEAD						1		X														
		A	S3-1	36	36	FYG	11/15/17	9.00								2		13'-9" X									SCHOOL BUS STOP AT HOMESTEAD WAY	X	
NB	1.035	A	W1-4MeR	36	36	FY	4/9/17	9.00								2			X								INSTALL 35' DOWNSTATION FROM EXISTING WARNING SIGN ASSEMBLY @ MP 1.042 NB		2
		A	VW-268	36	36	FY		9.00																			SLIP BASES REQUIRED SEE SHEET 4		2
		A	W13-1P	24	24	FY		4.00																			INSTALL ON LEFT POST	X	
NB	1.042	A					COMBINATION REVERSE CURVE/SIDE ROAD						1		X														
		A					NARROW UNDERPASS						1																
		A	W13-1P				35 M.P.H.						1																
SIGN SUMMARY SHEET							SHEET TOTALS	45.00	0.00	0	0	0	9	0	0	6		90.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	615.1	0.0	21	16	16	132	0	0	110		1630.0		0	0.0							

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Vernon142 NB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
VERNON VT-142 NB 5 SHEET **153** OF **264**