DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB VERNON VT ROUTE 142							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	1.083	A	W12-2				LOW CLEARANCE 13'-5"						1	X															
		A	W12-2	36	36	FY	11/21/17	9.00																		INSTALL ON RETAINED POSTS	X		
NB	1.115	A	OM3-R				11/14/17						1		X														
		A	OM3-R	12	36	FY		3.00								1		10'-0" X										X	
NB	1.128	B	OM3-L				11/14/17						1		X														
		B	OM3-L	12	36	FY		3.00								1		10'-6" X										X	
NB	1.165	A	W1-6	48	24	FY	11/15/17	8.00								2		12'-3" 12'-3" X									INSTALL 195' UPSTATION FROM EXISTING SIGN AT MP 1.128 NB	X		
NB	1.180	B	W1-6	48	24	FY	11/15/17	8.00								2		12'-6" 12'-3" X									INSTALL 50' DOWNSTATION FROM EXISTING HOMESTEAD WAY SIGN AT MP 1.190 NB	X		
NB	1.190	AB	D3-1				HOMESTEAD WAY						1		X												HOMESTEAD WAY (TH-35)			
NB	1.190	C	VR-017				LLL 24,000 LBS						1		X														
		C	R2-1				SPEED LIMIT 25				1		1																
		C	VR-017	24	30		11/15/17	5.00								1		13'-6" X									INSTALL AT EXISTING LEGAL LOAD LOCATION			T-70
		C	R2-1				SPEED LIMIT 25					1															INSTALL SALVAGED SIGN BELOW LEGAL LOAD			
NB	1.200	AB	D3-1	68	12		11/15/17	5.67								2		11'-6" 11'-0" X									INSTALL ON STOP SIGN SIDE OF INTERSECTION		8	
NB	1.200	D	R1-1				STOP						1		X														
							SHEET TOTALS	41.67	0.00	0	1	1	7	0	0	9		135.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	615.1	0.0	21	16	16	132	0	0	110		1630.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Vernon142 NB.xls**
PROJECT MANAGER: **D. MUNRO**
DESIGNED BY: **P. MCKECHNIE**
VERNON VT-142 NB 6
PLOT DATE: **2/27/2017**
DRAWN BY: **W. GORDON**
CHECKED **BRZEZOWSK**
SHEET **154** OF **264**