DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB VERNON VT ROUTE 142							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	5.190	A					FLASHING BEACON			1				X															
		A	W10-1				11/17/17						1																	
		A	W10-1	36	36			7.07																			INSTALL NEW SIGN ON RETAINED POST WITH EXISTING CONDUIT 36" DIAMATER	X		
NB	5.240	A	W1-10cL										1		X															
		A	W13-1P										1																	
		A	W1-10cL	36	36		11/17/17	9.00								2		17'-3" 17'-0" X										X		
		A	W13-1P	24	24			4.00																			INSTALL ON LEFT POST	X		
NB	5.310	A	W11-4	30	30		11/17/17	6.25								1		15'-9" X									INSTALL ±85' DOWNSTATION FROM EXISTING SIGN AT MP 5.326 NB	X		
			VW11-4P	30	18			3.75																				5	
NB	5.326	C	VR-017				LLL 24,000 LBS			1				X													GOVERNOR HUNT RD (TH-4)			
NB	5.326	AB											1		X															
		AB	D3-1	72	12		11/21/17	6.00								2		12'-3" 12'-0" X											8	
NB	5.326	B	W1-6				ONE DIRECTION LARGE ARROW						1		X															
		B	VD-700				MILE MARKER 1420 / 1318 / 0537				1		1															SALVAGE MILE MARKER TO MP 5.340 NB			
NB	5.326	B	W1-6	48	24		11/17/17	8.00								2		14'-6" 13'-9" X										X		
							SHEET TOTALS	44.07 SF	0.00 SF	2 EA	1 EA	0 EA	6 EA	0 EA	0 EA	7 EA		105.0 FT			0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	615.1	0.0	21	16	16	132	0	0	110		1630.0			0	0.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Vernon142 NB.xls**
PROJECT MANAGER: **D. MUNRO**
DESIGNED BY: **P. MCKECHNIE**
VERNON VT-142 NB 14
PLOT DATE: **2/27/2017**
DRAWN BY: **W. GORDON**
CHECKED **BRZEZOWSK**
SHEET **162** OF **264**