DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB VERNON VT ROUTE 142							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		A	VD-700				MILE MARKER 1420 / 1318 / 0800					1																	
NB	8.030	A					TRUCKS ENTERING						1		X														
		A	W7-3aP				NEXT 1 MILE						1																
NB	8.043	A	VW-202	30	30		11/15/17	6.25								1		15'-3" X							INSTALL SIGN 200' UPSTATION FROM EXISTING SIGN AT MP 8.005 NB			T-81
		A	W7-3aP	24	18			3.00																		X		
NB	8.105	A	W1-4R				RIGHT REVERSE CURVE						1		X														
NB	8.170	A	W11-2				PEDESTRIAN TRAFFIC						1		X														
		A	VW-207BP				BLIND PERSON (PLAQUE)						1																
		A	W16-7pL				LEFT DIAGONAL ARROW PLAQUE						1																
		C	VD-700				MILE MARKER 1420 / 1318 / 0822				1		1														SALVAGE MILE MARKER TO NEW POST AT SAME STATION			
		A	W11-2	30	30	FYG	11/14/17	6.25								2		16'-0" 16'-0" X								X		
		A	VW-207BP	24	18	FYG		3.00																			5	
		A	W16-7pL	24	12	FYG		2.00																		X		
		A	VD-700				MILE MARKER 1420 / 1318 / 0822					1														INSTALL ON LEFT POST			
NB	8.244	A	VD-701				BRIDGE / 6 / VT-142						1		X														
							SHEET TOTALS	20.50	0.00	0	1	2	8	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	615.1	0.0	21	16	16	132	0	0	110		1630.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Vernon142 NB.xls**
PROJECT MANAGER: **D. MUNRO**
DESIGNED BY: **P. MCKECHNIE**
VERNON VT-142 NB 18
PLOT DATE: **2/27/2017**
DRAWN BY: **W. GORDON**
CHECKED **BRZEZOWSK**
SHEET **166** OF **264**