DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
EB WALLINGFORD VT RTE 140							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
		A	W13-1P				25 MPH						1																
		A	W1-5R	30	30	FY	11/7/17	6.25								1		14'-3" X										X	
		A	W7-3aP	24	18	FY	NEXT ½ MILE	3.00																				X	
EB	2.347	A	W1-4R				RIGHT REVERSE CURVE						1		X														
EB	2.375	A	VW-285	30	30	FY	11/4/17	6.25					~~1~~		~~X~~	1		13'-0" X									INSTALL SIGN ±150' UPSTATION FROM EXISTING SIGN AT MP 2.347 EB		1	
EB	2.487	A	VD-701	6	10		BRIDGE 4 VT-140 11/4/17	0.42								1	7'-3" X												T-42
EB	2.488	A	OM3-R				RIGHT OBJECT MARKER						1		X														
		A	VD-701				4/9/18 BRIDGE 4 PLAQUE						1																	
		A	OM3-R	12	36	FY		3.00								1		9'-9" X										X	
EB	2.495	B	OM3-L	12	36	FY	11/13/17	3.00								1		10'-9" X									INSTALL ON UPSTATION END OF BRIDGE	X	
EB	2.524	A	W1-3R	30	30	FY	11/4/17	6.25								1		12'-3" X									INSTALL ±190' UPSTATION FROM BRIDGE PLAQUE AT MP 2.488 EB (ADJUST LOCATION UP TO 125' WEST IF LEDGE ENCOUNTERED)	X	
		A	W13-1P	18	18	FY	20 MPH	2.25																				X	
EB	2.556	B	W1-6R				11/4/17						1	X															
		B	W1-6R	48	24	FY		8.00																			INSTALL ON RETAINED POSTS	X	
							SHEET TOTALS	38.42	0.00	0	0	0	6	0	0	5		70.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	489.4	0.0	46	4	4	100	0	0	86		1250.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**

FILE NAME: **z16t041Wallingford140EB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
WALLINGFORD VT-140 EB 7 SHEET **203** OF **264**