DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
EB WALLINGFORD VT RTE 140							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
EB	3.790	A	W1-8L	18	24	FY	11/4/17	3.00								1		12'-0" X								INSTALL 160' UPSTATION FROM EXISTING RIGHT CHEVRON AT MP 3.760 EB	X		
EB	3.791	B	W1-8R	18	24	FY	11/4/17	3.00								1		12'-0" X								INSTALL 160' UPSTATION FROM EXISTING RIGHT CHEVRON AT MP 3.760 EB	X		
EB	3.800	A	W1-8L				CHEVRON						1		X														
EB	3.801	B	W1-8R				CHEVRON						1		X														
EB	3.805	A	W1-8L	18	24	FY	11/4/17	3.00								1		12'-0" X								INSTALL 240' UPSTATION FROM EXISTING RIGHT CHEVRON AT MP 3.760 EB	X		
EB	3.806	B	W1-8R	18	24	FY	11/4/17	3.00								1		12'-0" X								INSTALL 240' UPSTATION FROM EXISTING RIGHT CHEVRON AT MP 3.760 EB	X		
EB	3.820	A	W1-8L				CHEVRON						1		X														
		B	W1-8R				CHEVRON						1																
EB	3.820	A	W1-8L	18	24	FY	11/4/17	3.00								1		11'-3" X								INSTALL 320' UPSTATION FROM EXISTING RIGHT CHEVRON AT MP 3.760 EB	X		
EB	3.821	B	W1-8R	18	24	FY	11/4/17	3.00								1		12'-0" X								INSTALL 320' UPSTATION FROM EXISTING RIGHT CHEVRON AT MP 3.760 EB	X		
EB	3.835	A	W1-8L	18	24	FY	11/6/17	3.00								1		12'-0" X								INSTALL 400' UPSTATION FROM EXISTING RIGHT CHEVRON AT MP 3.760 EB	X		
EB	4.265	A	W2-2L				T-INTERSECTION SIDE ROAD						1		X														
EB	4.350	A	R2-1				SPEED LIMIT 50						1	X															
		A	R2-1	24	30		11/7/17	5.00																			INSTALL ON RETAINED POST	X		
EB	4.715	A	W2-1				CROSS ROAD						1		X														
							SHEET TOTALS	26.00	0.00	0	0	0	7	0	0	7		105.0		0	0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
							TOWN DIRECTIONAL TOTALS	489.4	0.0	46	4	4	100	0	0	86		1250.0		0	0.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**

FILE NAME: **z16t041Wallingford140EB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
WALLINGFORD VT-140 EB 10 SHEET **206** OF **264**