DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
EB WALLINGFORD VT RTE 140							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
EB	6.055	D	R1-1				4/9/18						1		X												SEWARD HILL RD (TH-84) (SECONDARY STOP SIGN AT INTERSECTION WITH VT 140)			
		D	R1-1	30	30			6.25								1		13'-6" X										X	
EB	6.056	B	W1-6L				11/2/17						1		X															
		B	W1-6L	48	24			8.00								2		13'-0" 12'-9" X										X	
EB	6.070	A	R15-1				RAILROAD CROSS BUCK			1				X													ON RAILROAD SIGNAL POLE			
EB	6.079	C	VR-017				11/1/17						1		X												BILL FOX RD (TH-71)			
		C	VR-017	24	30			5.00								1		13'-3" X												T-70
EB	6.085	AB					BILL FOX RD						1		X															
EB	6.085	D	R1-1				STOP						1		X												BILL FOX RD (TH-71)			
		C	VD-700				MILE MARKER 1400/1125/0609				1		1														SALVAGE TO NEW POST AT SAME STATION			
		AB	D3-1	42	12		Bill Fox Rd 11/2/17	3.50					~~1~~			1		13'-9" X								INSTALL ON TOP OF STOP SIGN		9	
		D	R1-1	30	30		11/1/17	6.25																				X	
		C	VD-700				MILE MARKER 1400/1125/0609					1															INSTALL SALVAGED MILE MARKER BACK TO BACK ON STOP SIGN POST			
EB	6.090	A	M2-1				JCT			1				X																
SIGN SUMMARY SHEET							SHEET TOTALS	29.00	0.00	2	1	1	7	0	0	5		75.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	489.4	0.0	46	4	4	100	0	0	86		1250.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Wallingford140EB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
WALLINGFORD VT-140 EB 14 SHEET **210** OF **264**