| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 4) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS | | EXISTING SIGNS | | | | EXIST POST | | NUMBER OF NEW POSTS | SQUARE STEEL (IN) | | | TUBULAR STEEL Ø (IN) | | | | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL LOCATION | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | "A" | "B" | RETAIN | SALVAGE FROM | SALVAGE TO | REMOVE | RETAIN | REMOVE | | 1.75 | 2.00 | 2.50 | 3.00 | 3.50 | 4.00 | 5.00 | | | SHSM | SIGN DETAILS SHEET # | STANDARD SHEET # |
| | | | | | | | | | | | | | | | | | (LB / FT) | | | (LB / FT) | | | | | | | | |
| | | | | | | | | | | | | | | | | | 1.88 | 2.42 | 3.35 | 7.60 | 9.00 | 10.80 | 14.60 | | | | | |
| **EB MT HOLLY VT RTE 140** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK | | | |
| EB | 0.000 | C | VD-024 | | | | Mount Holly \| Wallingford | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | C | VD-700 | | | | MILE MARKER 1400 / 1125 / 0634 | | | 1 | | | | | | | | | | | | | | | | | | |
| | | C | VD-700 | | | | MILE MARKER 1400 / 1112 / 0000 | | | 1 | | | | | | | | | | | | | | | | | | |
| EB | 0.041 | A | M2-1 | | | | JCT | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | A | | | | | VERMONT 103 | | | 1 | | | | | | | | | | | | | | | | | | |
| | | A | M4-6 | | | | END | | | 1 | | | | | | | | | | | | | | | | | | |
| | | A | | | | | VERMONT 140 | | | 1 | | | | | | | | | | | | | | | | | | |
| EB | 0.082 | A | W3-1 | | | | STOP AHEAD | | | 1 | | | | X | | | | | | | | | | | | | | |
| EB | 0.112 | A | VD1-1A | | | | Mount Holly 2 --> | | | 1 | | | | X | | | | | | | | | | | | | | |
| | | A | VD1-1A | | | | Ludlow 11 --> | | | 1 | | | | | | | | | | | | | | | | | | |
| EB | 0.143 | A | R1-1 | | | | STOP | | | | | | 1 | | X | | | | | | | | | | | | | |
| | | B | VD-700 | | | | MILE MARKER 1030 / 1112 / 0756 | | | | 1 | | 1 | | | | | | | | | | | | | | | |
| | | A | R1-1 | 30 | 30 | | STOP 11/2/17 | 6.25 | | | | | | | | 1 | 13'-6" X | | | | | | | | | X | | |
| | | B | VD-700 | ~~6~~ | ~~10~~ | | MILE MARKER 1030 / 1112 / 0756 | ~~0.42~~ | | | | 1 | | | | | | | | | | | | | | INSTALL SALVAGED MILE MARKER BACK TO BACK ON STOP SIGN | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| **SIGN SUMMARY SHEET** | | | | | | | SHEET TOTALS | 6.67 | 0.00 | 10 | 1 | 1 | 2 | 0 | 0 | 1 | 15.0 | | | 0 | 0.0 | 0.0 | 0.0 | 0.0 | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | | EA | LB | LB | LB | LB | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN DIRECTIONAL TOTALS | 6.7 | 0.0 | 10 | 1 | 1 | 2 | 0 | 0 | 1 | 15.0 | | | 0 | 0.0 | | | | | | | | |

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Mt HollvVT140 EB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
MOUNT HOLLY VT-140 EB 1 SHEET **235** OF **264**