DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB WALLINGFORD VT RTE 155							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	0.012	A	W3-1				STOP AHEAD			1				X														
NB	0.052	A	VD1-1A				<-- Wallingford 6			1				X														
		A	VD1-1A				Ludlow 11 -->			1																		
NB	0.082	A	OM3-R				11/15/17						1		X													
		A	OM3-R	12	36			3.00								1		9'-9" X									X	
NB	0.132	A	R1-1				STOP			1				X														
		A	VD-700				MILE MARKER 1400/1125/0620			1				X													NOTE: PROJECT SUSPENDS HERE AT EASTERN JUNCTION WITH VT 140			
NB	0.161	A	R2-1				SPEED LIMIT 30 10/27/17						1		X												NOTE: PROJECT RESUMES HERE AT WESTERN JUNCTION WITH VT 140			
		A	R2-1	24	30			5.00								1		13'-3" X									THINNING AND TRIMMING	X		
NB	0.197	A	W5-2										1		X														
		A	VD-700				NARROW BRIDGE 1550 1125 0020 10/27/17						1																	
		A	W5-2	30	30			6.25								1		14'-0" X									X	
		A	VD-700	6	10			0.42																					T-44
NB	0.263	A	W3-1	30	30		10/27/17	6.25								1		14'-3" X									INSTALL 20' DOWNSTATION OF EXISTING SIGN AT MP 0.267	X		
NB	0.267	A	W3-1				STOP AHEAD						1		X														
							SHEET TOTALS	20.92 SF	0.00 SF	5 EA	0 EA	0 EA	5 EA	0 EA	0 EA	4 EA		60.0 FT		0 EA	0.0 LB	0.0 LB	0.0 LB	0.0 LB					
							TOWN DIRECTIONAL TOTALS	42.3	0.0	9	1	1	11	0	0	10		145.0		0	0.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Wallingford155NB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
WALLINGFORD VT-155 NB 1 SHEET **257** OF **264**