DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB WALLINGFORD VT RTE 155							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	0.142	AB	D3-1A										1		X												**NOTE: PROJECT RESUMES HERE AT EASTERN JUNCTION WITH VT 140**			
		AB	D3-1A	42	12		Weston Rd 11/14/17	3.50								1		11'-3" X											10	
SB	0.112	F	R2-1				SPEED LIMIT 35			1				X																
SB	0.087	F	VD2-1				Weston 14				1		1		X												REMOVE SIGN AND SALVAGE TO NEW POSTS			
		F	VD2-1				Londonderry 19				1		1														REMOVE SIGN AND SALVAGE TO NEW POSTS			
		F	M3-3				SOUTH				1		1														REMOVE SIGN AND SALVAGE TO NEW POSTS			
		F	VM1-5				VERMONT 155				1		1														REMOVE SIGN AND SALVAGE TO NEW POSTS			
		F	VD2-1				11/14/17 Weston 14					1				2		17'-3" 15'-6" X									INSTALL SALVAGED SIGN ON NEW POSTS			
		F	VD2-1				Londonderry 19					1															INSTALL SALVAGED SIGN ON NEW POSTS			
		F	M3-3				SOUTH					1															INSTALL SALVAGED SIGN ON NEW POSTS			
		F	VM1-5				VERMONT 155					1															INSTALL SALVAGED SIGN ON NEW POSTS			
SB	0.000	G	VD-024				MOUNT HOLLY | WALLINGFORD						1		X																
		G	VD-700				MILE MARKER 1550 / 1112 / 0760						1																			
		G	VD-700				MILE MARKER 1550 / 1125 / 0000						1																			
SIGN SUMMARY SHEET							SHEET TOTALS	3.50	0.00	1	4	4	8	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	62.8	0.0	3	5	5	22	0	0	14		205.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Wallingford155SB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
WALLINGFORD VT-155 SB 3 SHEET **262** OF **264**