DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
NB LUDLOW VT ROUTE 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
NB	2.380	C	R7-201				TOW AWAY ZONE PLAQUE						1		X												RETURN SIGN TO TOWN			
		C	R7-1				NO PARKING ANYTIME <--->						1														RETURN SIGN TO TOWN			
NB	2.415	A	R2-1				SPEED LIMIT 30						1		X															
NB	2.417	C	R7-201				NO PARKING ANYTIME <--->						1		X												RETURN SIGN TO TOWN			
		C	R7-1				TOW AWAY ZONE PLAQUE						1														RETURN SIGN TO TOWN			
NB	2.470	C	R7-1				NO PARKING ANYTIME <--->						1		X												RETURN SIGN TO TOWN			
		C	R7-201				TOW AWAY ZONE PLAQUE						1														RETURN SIGN TO TOWN			
NB	2.509	C	R7-1				NO PARKING ANYTIME <--->						1		X												RETURN SIGN TO TOWN			
		C	R7-201				TOW AWAY ZONE PLAQUE						1														RETURN SIGN TO TOWN			
		A	R2-1	24	30		SPEED LIMIT 30 8/16/17	5.00								1		14'-0" X									X		
NB	2.544	C	R7-1				NO PARKING ANYTIME <--->						1		X												RETURN SIGN TO TOWN			
		C	R7-201				TOW AWAY ZONE PLAQUE						1														RETURN SIGN TO TOWN			
NB	2.569	A	VD1-1Sa				<-- OKEMO MTN. SKI AREA						1		X															
		A	VD1-1Sa	72	12		Okemo Mtn SKI AREA 8/16/17	6.00								2		13'-9" 12'-9" X											3	
NB	2.584	C	R7-1				NO PARKING ANYTIME <--->						1		X												RETURN SIGN TO TOWN			
SIGN SUMMARY SHEET							SHEET TOTALS	11.00	0.00	0	0	0	13	0	0	3		45.0		0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	754.3	0.0	42	13	13	190	0	0	65		945.0		0	0.0								

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Ludlow103 NB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
LUDLOW VT-103 NB 18 SHEET **50** OF **264**