DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB LUDLOW VT ROUTE 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	2.791	G	R7-1				NO PARKING ANYTIME <--->						1		X											RETURN SIGN TO TOWN			
		G	R7-201				TOW AWAY ZONE PLAQUE						1													RETURN SIGN TO TOWN			
SB	2.781	FE	D3-1				TAPPER ST						1	~~X~~	X											TAPPER ST (TH-363)			
		H	R1-1				STOP						1																
		G	VD-700				MILE MARKER 1030/1410/0277			~~1~~	1	1	1																
		FE	D3-1	42	12		Tapper St / STOP 8/24/17	3.50								1	11'-6" X									INSTALL ON TOP OF STOP SIGN		6	
		H	R1-1	30	30			6.25																		~~INSTALL ON RETAINED POST~~	X		
SB	2.771	F	W11-2				PEDESTRIAN TRAFFIC						1	X															
		F	W7-3aP				NEXT 1 MILE						1																
		F	W11-2	30	30	FYG	NEXT 1 MILE 8/23/17	6.25																		INSTALL ON RETAINED POST PROVIDE 7' MINIMUM CLEAR HEIGHT	X		
		F	W7-3aP	24	18	FYG		3.00																			X		
SB	2.766	G	R7-1				NO PARKING ANY TIME 8/23/17 NO PARKING ANYTIME <--->						1		X															
		G	R7-201				TOW-AWAY ZONE TOW AWAY ZONE PLAQUE						1																		
		G	R7-1	12	18			1.50								1	12'-3" X									NOTE: DOUBLE HEADED ARROW. PROVIDE 7' MINIMUM CLEAR HEIGHT	X		
		G	R7-201	12	6			0.50																			X		
SIGN SUMMARY SHEET							SHEET TOTALS	21.00	0.00	1	0	0	8	0	0	1	15.0			0	0.0	0.0	0.0	0.0					
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT			EA	LB	LB	LB	LB					
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	502.1	0.0	48	5	5	120	0	0	62	870.0			2	217.0								

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Ludlow103 SB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
LUDLOW VT-103 SB 6 SHEET **67** OF **264**