DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION SHSM	SIGN DETAIL LOCATION SIGN DETAILS SHEET #	SIGN DETAIL LOCATION STANDARD SHEET #
SB LUDLOW VT ROUTE 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																				"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
SB	1.949	F	VD-701										1		X														
		F	VD-701	6	10		BRIDGE 25 VT-103 8/28/17	0.42								1	6'-9" X												T-42
SB	1.890	F	W11-2				PEDESTRIAN TRAFFIC						1		X														
		F	W16-7pL				LEFT DIAGONAL ARROW PLAQUE						1																
SB	1.875	F	W11-2	30	30	FYG	8/30/17	6.25								1		14'-3" X								~~INSTALL POST IN GRASS BEHIND SIDEWALK 5' UPSTATION OF BRICK WALKWAY AT CROSSWALK~~ INSTALLED AT EXISTING LOCATION	X	
		F	W16-7pL	24	12	FYG		2.00																		PROVIDE 7' MINIMUM CLEAR HEIGHT	X	
SB	1.865	G					RESERVED PARKING (HANDICAP SYMBOL)						1		X												RETURN SIGN TO TOWN		
SB	1.856	FE	D3-1				MEADOW ST						1	~~X~~	X												MEADOW ST (TH-326)		
		H	R1-1				STOP						1																
		F	VD-700				MILE MARKER 1030/1410/0185			~~1~~	1	1	1																
		FE	D3-1	42	12		Meadow St 8/21/17	3.50								1		13'-3" X									INSTALL ON TOP OF STOP SIGN		7
		H	R1-1	30	30		STOP	6.25																		~~INSTALL ON RETAINED POST~~	X	
SB	1.855	G					NO PARKING BUS STOP						1		X												RETURN SIGN TO TOWN		
SB	1.840	G	R7-108				2 HR PARKING 8:30 AM TO 5:30 PM <--->			1				X															
SIGN SUMMARY SHEET							SHEET TOTALS	18.42	0.00	2	0	0	7	0	0	2		25.0		0	0.0	0.0	0.0	0.0				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	502.1	0.0	48	5	5	120	0	0	62		870.0		2	217.0							

PROJECT NAME: **STATEWIDE-SOUTH REGION**
PROJECT NUMBER: **STPG SIGN(57)**
FILE NAME: **z16t041Ludlow103 SB.xls** PLOT DATE: **2/27/2017**
PROJECT MANAGER: **D. MUNRO** DRAWN BY: **W. GORDON**
DESIGNED BY: **P. MCKECHNIE** CHECKED **BRZEZOWSK**
LUDLOW VT-103 SB 16 SHEET **77** OF **264**