

DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	SHSM	SIGN DETAILS SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
																	1.88	2.42	3.35		7.60	9.00	10.80			14.60			
SB LUDLOW VT ROUTE 103							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK							
SB	1.794	F	R2-1				SPEED LIMIT 30 SPEED LIMIT 30						1		X														
SB	1.756	F	R2-1	24	30		SPEED LIMIT 30 8/30/17	5.00								1		12'-9" X							INSTALL IN GRASS BEHIND SIDEWALK 10' UPSTATION FROM UTILITY POLE. PROVIDE 7' MINIMUM CLEAR HEIGHT	X			
SB	1.700	F	W11-2				PEDESTRIAN TRAFFIC						1	X	X														
		F	W16-7pL				LEFT DIAGONAL ARROW PLAQUE						1																
SB	1.700	F	D3-1	28	12		Mill St 8/14/17	2.33								1		11'-0" X							MILL ST (TH-324) INSTALL ON RETAINED POST AT LOCATION OF REMOVED PEDESTRIAN WARNING SIGN. PROVIDE 7' MINIMUM CLEAR HEIGHT. INSTALLED ON NEW POST		7		
SB	1.694	F	W11-2	30	30	FYG	8/30/17	6.25								1		14'-0" X							INSTALL AT LOCATION OF EXISTING STOP SIGN AT MP 1.694 SB. PROVIDE 7' MINIMUM CLEAR HEIGHT INSTALLED AT EXISTING PED TRAFFIC SIGN LOCATION	X			
		F	W16-7pL	24	12	FYG		2.00																		X			
SB	1.694	FE	D3-1				MILL ST						1		X														
		H	R1-1				STOP						1																
		F	VD-700				MILE MARKER 1030/1410/0168				1		1												INSTALLED AT EXISTING STOP SIGN LOCATION INSTALL 8' FURTHER DOWN MILL STREET. PROVIDE 7' MINIMUM CLEAR HEIGHT				
		H	R1-1	30	30		STOP 8/30/17	6.25								1		12'-3" X							INSTALL SALVAGED MILE MARKER BACK TO BACK ON STOP SIGN POST	X			
		F	VD-700				MILE MARKER 1030/1410/0168					1																	
SB	1.680	G	R7-1				NO PARKING ANY TIME				1		1	X	X										EXISTING SIGN AND POST RETAINED				
		G	R7-1	12	18		NO PARKING ANY TIME	1-50								1		X							NOTE: DOUBLE HEADED ARROW PROVIDE 7' MINIMUM CLEAR HEIGHT	X			
SIGN SUMMARY SHEET						SHEET TOTALS		23.33	0.00	0	1	1	7	0	0	4		60.0		0	0.0	0.0	0.0	0.0	PROJECT NAME: STATEWIDE-SOUTH REGION				
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT		EA	LB	LB	LB	LB	PROJECT NUMBER: STPG SIGN(57)				
																								FILE NAME: z16t041Ludlow 103 SB.xls		PLOT DATE: 2/27/2017			
VERMONT AGENCY OF TRANSPORTATION						TOWN DIRECTIONAL TOTALS		502.1	0.0	48	5	5	120	0	0	62		870.0		2	217.0				PROJECT MANAGER: D. MUNRO				
																							DESIGNED BY: P. MCKECHNIE			DRAWN BY: W. GORDON			
																							CHECKED: BRZEZOWSKI						
																							SHEET 78 OF 264						