

DIRECTION	MILEPOINT	LOCATION CODE (SHEET 4)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL LOCATION			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	SHSM	SIGN DETAILS SHEET #	STANDARD SHEET #
																	(LB / FT)				(LB / FT)								
																	1.88	2.42	3.35		7.60	9.00	10.80			14.60			
WB WALLINGFORD VT RTE 140							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS BOOK							
			H	R1-1	30	30	11/8/17	6.25															INSTALL ON RETAINED POST	X					
			G	VD-700	6	10		0.42															INSTALL BACK TO BACK ON STOP SIGN POST			T-44			
WB	0.138	FE					PROSPECT ST					1	X																
		GH					SCHOOL ST					1																	
		FE	D3-1		42	12	11/8/17	3.50						1	11'-0" X										9				
WB	0.130	F	W11-2				11/8/17					1	X																
		F	W16-7p					1																					
		F	W11-2	30	30	FYG		11/9/17	6.25						1	14'-0" X								INSTALL IN GREEN STRIP AT SAME LOCATION PROVIDE 7' CLEAR HEIGHT	X				
		F	W16-7p	24	12	FYG			2.00															X					
WB	0.128	G	R8-3	24	24		 11PM-7AM NOV. 15-APR. 1 	4.00						1	13'-3" X									INSTALL SIGN ±10' FROM EXISTING SIGN AT MP 0.130 WB BETWEEN SIDEWALK AND CURB.	X				
		G		24	10			1.67																4					
		G	M4-14	24	12			2.00																X					
WB	0.100	F	W3-3									1	X																
		F	W3-3	30	30			6.25						1	13'-6" X	X								INSTALL IN GRASS BETWEEN CURB AND SIDEWALK. PROVIDE 7' CLEAR HEIGHT	X				
WB	0.084	G	VR-017				LLL 24,000 LBS					1	X																
SIGN SUMMARY SHEET							SHEET TOTALS	32.33	0.00	0	0	0	6	0	0	4	60.0	0	0.0	0.0	0.0	0.0	PROJECT NAME: STATEWIDE-SOUTH REGION						
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	EA	LB	LB	LB	LB	PROJECT NUMBER: STPG SIGN(57)						
																										FILE NAME: z16t041Wallinaford140WB.xls PLOT DATE: 2/27/2017			
							VERMONT AGENCY OF TRANSPORTATION	TOWN DIRECTIONAL TOTALS	572.0	0.0	35	2	2	128	0	0	93	1325.0	2	183.0					DRAWN BY: W. GORDON DESIGNED BY: P. MCKECHNIE WALLINGFORD VT-140 WB 17 CHECKED BY: BRZEWOSKI SHEET 231 OF 264				