DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ST ALBANS TOWN			**VT36**	**EB**			FYG-FLUORESCENT YELLOW-GREEN																			"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
	0.770	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		13.50 X								TH 1			T-70
EB	0.770	A	VD3-1	42	12		Lake Rd	3.50								~~2~~ 1		10.50 X 10.50			SIGN TOO BIG TO INSTALL ABOVE STOP ADDED POST					TH 1 INSTALL STREET SIGN ABOVE STOP SIGN		5	
		C	VD3-1	72	12		Georgia Shore Rd	6.00																		TH 1		5	
		D	R1-1	30	30		STOP			1				1												TH 1			
		A	VD-700	6	10		MM 0036, 06130, 0077			1																TH 1			
EB	0.805	A	M3-2	24	12		EAST			1				1															
		A	VM1-5	24	24		VT 36			1																			
EB	0.830	A	VR-020	24	30		NO PARKING ON TRAVELED LANE			1				1												REQUIRES VEGETATION CLEARING			
		B	VR-020	24	30		NO PARKING ON TRAVELED LANE			1																			
		A	R2-1	24	30		SPEED LIMIT 30				1		1													*SALVAGE SIGN TO EB MM 0.730*			
EB	0.840	D	R1-1	30	30		STOP						1		1											TH 48			
EB	0.840	C	VR-017	24	30		LLL 24,000 LBS				1	1	1	~~1~~	1	1		X 13.25			NEW POST NEEDED					TH 48			
		C	VD-700	6	10		MM 0036, 0613, 0085			1																TH 48			
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																		TH 48			T-70
EB	0.845	A	VD3-1	30	12		CHUBB ST			1	1	1	1	~~1~~				X 10.25								TH 48			
SIGN SUMMARY SHEET							SHEET TOTALS	19.50	0.00	8	1	0	3	~~5~~	~~1~~	~~2~~		~~30~~		0	0								
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
VERMONT AGENCY OF TRANSPORTATION											3	2	4	3	2	4		58										
							TOWN TOTALS	326.25	0.00	76	7	7	62	52	29	45		675		1	210								

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**

FILE NAME: **z16T042 VT36-ST ALBANS EB.** PLOT DATE: **3/10/2017**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
ST ALBANS TOWN VT36 EB 5 SHEET **18** OF **146**