| DIR | MILEPOINT | LOCATION CODE | MUTCD CODE | WIDTH | HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (in) 1.75 (LB / FT) 1.88 | SQUARE STEEL (in) 2.00 (LB / FT) 2.42 | SQUARE STEEL (in) 2.50 (LB / FT) 3.35 | FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHSM | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **FAIRFIELD** | | | **VT36** | **EB** | | | FYG-FLUORESCENT YELLOW-GREEN | | | | | | | | | | | | | | | | | | | | "SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS | | | |
| EB | 8.493 | A | VD-062B | 72 | 16 | | FAIRFIELD COMM. ===> | | | 1 | | | | 2 | | | | | | | | | | | | | CENTER SCHOOL ST. 1 | | | |
| EB | 8.548 | A | W1-4L | 30 | 30 | | LEFT REVERSE CURVE | | | | | | 1 | | 2 | | | | | | | | | | | | | | | |
| | | A | VW-133R | 30 | 30 | | HIDDEN DRIVE RIGHT | | | | | | 1 | | | | | | | | | | | | | | | | | |
| EB | 8.558 | A | VW-133R | 30 | 30 | | | 6.25 | | | | | | | | 2 | | | 16.00 X | | | | | | | INSTALL SIGN ASSEMBLY 50 FEET EAST OF EXISTING SIGN ASSEMBLY | | | T-81 |
| | | A | W1-3R | 30 | 30 | | | 6.25 | | | | | | | | | | | | | | | | | | | X | | |
| | | A | W13-1P | 18 | 18 | | | 2.25 | | | | | | | | | | | | | | | | | | | X | | |
| EB | 8.673 | A | VD3-1 | 48 | 9 | | ELM BROOK RD TH47 | | | | | | 1 | | 1 | | | | | | | | | | | | TH 47 | | | |
| | | A | VD3-1 | 72 | 12 | | | 6.00 | | | | | | | | 2 | | 11.25 X 12.25 | | | | | | | | TH 47 | | 6 | |
| EB | 8.673 | C | VR-017 | 24 | 30 | | LLL 24,000 LBS | | | 1 | | | | 1 | | | | | | | | | | | | | TH 47 | | | |
| | | C | VD-701 | 6 | 10 | | BRIDGE 46 VT 36 | | | 1 | | | | | | | | | | | | | | | | | TH 47 | | | |
| EB | 8.683 | D | R1-1 | 30 | 30 | | | 6.25 | | | | | | | | 1 | | | 13.50 X | | | | | | | TH 47. INSTALL SIGN 170 FEET *NORTH FROM UTILITY POLE* | X | | |
| EB | 8.723 | A | W1-6L | 48 | 24 | | <=== LARGE ARROW LEFT | | | | | | 1 | 2 | | | | | | | | | | | | | | | | |
| | | A | W1-6L | 48 | 24 | | | 8.00 | | | | | | | | | | | | | | | | | | | REQUIRES VEGETATION CLEARING | X | | |
| EB | 8.723 | A | W1-6R | 48 | 24 | | ===> LARGE ARROW RIGHT | | | | | | 1 | 2 | | | | | | | | | | | | | | | | |
| | | A | W1-6R | 48 | 24 | | | 8.00 | | | | | | | | | | | | | | | | | | | REQUIRES VEGETATION CLEARING | X | | |
| | | | | | | | SHEET TOTALS | 43.00 | 0.00 | 3 | 0 | 0 | 5 | 7 | 3 | 5 | | | ~~75~~ | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | | FT | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | 53.00 | | | | | | | | | | |
| | | | | | | | TOWN TOTALS | 461.50 | 0.00 | 25 | 16 | 16 | 87 | 32 | 60 | 92 | | | 1380 | | | | | | | | | | |

## SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**

FILE NAME: **z16T042 VT36-FAIRFIELD EB.x**
PROJECT MANAGER: **B. BRESLEND**
DESIGNED BY: **O. DALMER**
FAIRFIELD VT36 EB 10

PLOT DATE: **3/10/2017**
DRAWN BY: **O. DALMER**
CHECKED BY: **B. BRESLEND**
SHEET **51** OF **146**