DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
FAIRFIELD			**VT36**	**WB**			FYG-FLUORESCENT YELLOW-GREEN																				"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	9.978	F	W3-5a	30	30		REDUCED SPEED AHEAD						1		1												TEXT			
		F	W3-5	36	36			9.00								2		13.50 X 14.50									X		
WB	9.963	H	VD-024	72	10		FAIRFIELD / BAKERSFIELD						1		1															
		H	VD-700	6	10		MM 0360, 0605, 9956				1		1														SALVAGE SIGNS ACROSS ROAD UNDER "BAKERSFIELD / FAIRFIELD" TOWN LINE SIGN			
		H	VD-700	6	10		MM 0360, 0601, 0000				1		1																	
WB	9.933	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		1												TEXT			
		F	VW-133R	30	30			6.25								1		14.00 X										T-81
WB	9.868	F	VD-018A	30	18		EAST FAIRFIELD						1		1												FAIRFIELD 5			
		F	VD-018A	36	24			6.00								2		11.50 X 11.75								REQUIRES VEGETATION CLEARING			T-95
WB	9.763	F	R2-1	24	30		SPEED LIMIT 35						1		1															
		F	VD-700	6	10		MM 0360, 0605, 0980				1	1	1			1	10.00 X													
WB	9.733	F	R2-1	30	36			7.50								1		14.50 X								INSTALL SIGN 160 FT WEST OF EXISTING LOCATION. REQUIRES VEGETATION CLEARING	X		
WB	9.603	F	W11-8	30	30		FIRE ENGINE						1		1															
		F	W11-8	30	30			6.25								1		14.50 X								INSTALL SIGN A MINIMUM OF 10 FEET FROM UTILITY POLE	X		
WB	9.538	F	VD3-1	24	6		NEW ST TH36						1		1												TH 36			
							SHEET TOTALS	35.00 SF	0.00 SF	0 EA	3 EA	1 EA	10 EA	0 EA	7 EA	8 EA		~~120~~ FT											
							TOWN TOTALS	351.58 SF	0.00 SF	16 EA	7 EA	5 EA	55 EA	24 EA	35 EA	64 EA		104.25 960 FT										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**

FILE NAME: **z16T042 VT36-FAIRFIELD WB.dgn** PLOT DATE: **3/10/2017**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
FAIRFIELD VT36 WB 1 SHEET **56** OF **146**