







| DIR | MILEPOINT | LOCATION CODE | MUTCD CODE | WIDTH | HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS | | EXISTING SIGNS | | | EXIST POST | | NUMBER OF NEW POSTS | SQUARE STEEL (in) | | | TUBULAR STEEL Ø (IN) | | | | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL | | | | |
|----------------------------------|-----------|---------------|-------------|-----------|--------|------------------|--|-----------|------|----------------|--------------|------------|------------|--------|---------------------|-------------------|-----------|------|----------------------|------------------------|--|------------------------------------|---------------------|---------|-------------|------|----------------|------------------------|----------------------------|
| | | | | | | | | "A" | "B" | RETAIN | SALVAGE FROM | SALVAGE TO | REMOVE | RETAIN | | REMOVE | 1.75 | 2.00 | 2.50 | FOUNDATION | 3.00 | 3.50 | | | 4.00 | 5.00 | DETAIL IN SHSM | DETAIL ON SHEET NUMBER | DETAIL ON STD SHEET NUMBER |
| | | | | | | | | | | | | | | | | | (LB / FT) | | | | (LB / FT) | | | | | | | | |
| BAKERSFIELD | | | VT36 | EB | | | FYG-FLUORESCENT YELLOW-GREEN | | | | | | | | | | | | | | "SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS | | | | | | | | |
| EB | 0.000 | C | VD-024 | 72 | 10 | |  | 5.00 | | | | | | 2 | 24.00 | X | | | | | INSTALL SIGN ASSEMBLY 10 FEET WEST OF WESTERN END OF GUARDRAIL | | | T-94 | | | | | |
| | | C | VD-700 | 6 | 10 | | MM 0360, 0601, 0000 | | | | 1 | | | | | | | | | | SALVAGE SIGN ON NEW POST FROM FAIRFIELD WB MM 9.963 | | | | | | | | |
| | | C | VD-700 | 6 | 10 | | MM 0360, 0605, 9956 | | | | 1 | | | | | | | | | | SALVAGE SIGN ON NEW POST FROM FAIRFIELD WB MM 9.963 | | | | | | | | |
| EB | 0.124 | A | OM3-R | 12 | 36 | | RIGHT OBJECT MARKER | 3.00 | | 4 | | 1 | 4 | | 11.00 | | | | | | REPLACE SIGN | | | | | | | | |
| EB | 0.134 | B | OM3-L | 12 | 36 | | LEFT OBJECT MARKER | 3.00 | | 4 | | 1 | 1 | | | | | | | | REPLACE SIGN | | | | | | | | |
| EB | 0.484 | A | W5-2 | 30 | 30 | | NARROW BRIDGE | | | | | 1 | 1 | | | | | | | | | | | | | | | | |
| EB | 0.544 | A | W5-2 | 36 | 36 | |  | 9.00 | | | | | | 2 | 17.00 | X | | | | | INSTALL SIGN 320 FEET EAST OF EXISTING SIGN ASSEMBLY | X | | | | | | | |
| EB | 0.629 | A | OM3-R | 12 | 36 | | RIGHT OBJECT MARKER | | | | | 1 | 1 | | | | | | | | | | | | | | | | |
| | | A | OM3-R | 12 | 36 | |  | 3.00 | | | | | | 1 | 11.25 | X | | | | | | X | | | | | | | |
| EB | 0.634 | B | OM3-L | 12 | 36 | | LEFT OBJECT MARKER | | | | | 1 | 1 | | | | | | | | | | | | | | | | |
| | | B | OM3-L | 12 | 36 | |  | 3.00 | | | | | | 1 | 11.25 | X | | | | | | X | | | | | | | |
| EB | 0.644 | A | W1-2R | 30 | 30 | | RIGHT CURVE | | | | | 1 | 1 | | | | | | | | | | | | | | | | |
| EB | 2.089 | A | W3-5 | 36 | 36 | |  | 9.00 | | | | | | 2 | 16.25 | X | | | | | INSTALL SIGN 80 FEET EAST OF UTILITY POLE | X | | | | | | | |
| EB | 2.239 | A | R2-1 | 24 | 30 | | SPEED LIMIT 40 | | | | | 1 | 1 | | | | | | | | | | | | | | | | |
| | | A | R2-1 | 30 | 36 | |  | 7.50 | | | | | | 2 | 14.00 | X | 14.00 | | | | | | X | | | | | | |
| SIGN SUMMARY SHEET | | | | | | | SHEET TOTALS | 36.50 | 0.00 | 2 | 0 | 2 | 5 | 2 | 5 | 10 | 150 | | | | | PROJECT NAME: STATEWIDE- NORTHWEST | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | FT | | | | PROJECT NUMBER: STPG SIGN (58) | | | | | | | | |
| VERMONT AGENCY OF TRANSPORTATION | | | | | | | TOWN TOTALS | 42.50 | | | | | 7 | | | | 151.25 | | | | FILE NAME: z16t042vt36-BAKERSFIELD EB. | PLOT DATE: 3/10/2017 | | | | | | | |
| | | | | | | | | 79.50 | 0.00 | 4 | 1 | 3 | 14 | 4 | 11 | 18 | 270 | | | | PROJECT MANAGER: B. BRESLEND | DRAWN BY: O. DALMER | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | DESIGNED BY: O. DALMER | CHECKED BY: B. BRESLEND | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | BAKERSFIELD VT36 EB 1 | SHEET 66 | OF 146 | | | | | | | |