DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL DETAIL ON STD SHEET NUMBER
BAKERSFIELD			**VT36**	**WB**			FYG-FLUORESCENT YELLOW-GREEN																			"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
WB	0.489	E	W5-2	30	30		NARROW BRIDGE						1		1														
WB	0.129	E	OM3-R	12	36		RIGHT OBJECT MARKER						1		1														
WB	0.124	E	OM3-L	12	36		LEFT OBJECT MARKER						1		1														
WB	0.084	G	VR-017	24	30		LLL 24,000 LBS						1	1												TH 28			
		G	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00																		TH 28			T-70
WB	0.069	F	VD3-1	42	9		LAWYER RD TH28						1	1												TH 28. SIGN MOUNTED BACK TO BACK			
		F	VD3-1	42	9		LAWYER RD TH28						1													TH 28. SIGN MOUNTED BACK TO BACK			
		H	R1-1	30	30		STOP			1																TH 28. VEGETATION CLEARING REQUIRED			
		G	VD-700	6	10		MM 0360,0601, 0010			1																TH 28			
WB	0.069	F	VD3-1	66	12		Lawyer Rd TH28	5.50								2		9.50 X 10.75								TH 28. PLACE SIGN 10 FEET NORTH FROM EXISTING STOP SIGN		7	

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in)	TUBULAR STEEL Ø (IN)
SHEET TOTALS	10.50	0.00	2	0	0	6	2	3	2	~~30~~	
	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT	
										20.25	
TOWN TOTALS	82.00	0.00	3	1	1	21	5	13	16	240	

PROJECT NAME: STATEWIDE- NORTHWEST
PROJECT NUMBER: STPG SIGN (58)
FILE NAME: z16T042VT36BAKERSFIELD WI
PROJECT MANAGER: B. BRESLEND
DESIGNED BY: O. DALMER
BAKERSFIELD VT36 WB 3
PLOT DATE: 3/10/2017
DRAWN BY: O. DALMER
CHECKED BY: B. BRESLEND