DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
FAIRFAX			**VT104**	**NB**			FYG-FLUORESCENT YELLOW-GREEN																				"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
	5.192	A	VD-700	6	10		MM 0104, 0604, 0529				1	1	1			1		13.25 X								TH 51. SALVAGE SIGN ON NEW POST IN EXISTING LOCATION			
		D	R1-1	30	30			6.25																		TH 51	X		
NB	5.192	A	W1-6L	48	24		<=== LEFT						1	2												LARGE ARROW			
		A	W1-6L	48	24			8.00																			X		
NB	5.194	B	W1-6R	48	24		RIGHT ===>						1	2												LARGE ARROW			
		B	W1-6R	48	24			8.00																			X		
NB	5.198	D	R1-1	30	30		STOP MM			1	1	1	1	~~1~~				13.25 X								DAMAGED POST REPLACED			
NB	5.233	A	VD1-1A	72	10		<--- FAIRFAX SCHOOLS			1				2												REQUIRES VEGETATION CLEARING			
NB	5.303	A	R2-1	24	30		SPEED LIMIT 30			1				1												REQUIRES VEGETATION CLEARING			
NB	5.598	A	R2-1	24	30		SPEED LIMIT 30					1				1		13.25 X								SALVAGE SIGN FROM SB MM 6.088. INSTALL 130 FT SOUTH FROM EXISTING "FIRE ENGINE" SIGN & 10 FT MINIMUM FROM DRIVEWAY			
NB	5.618	A	VD3-1	36	6		FIREMAN'S POND RD			1				1												PRIVATE ROAD			
NB	5.623	A	W11-8	30	30		FIRE ENGINE						1	1												SYMBOL			
		A	W11-8	30	30			6.25																			X		
NB	5.748	A	R2-1	24	30			5.00								1		14.75 X								INSTALL SIGN 55 FEET SOUTH FROM EXISTING "LLL 24K LBS " SIGN AND 10 FEET MINIMUM FROM UTILITY POLE	X		
NB	5.758	C	VR-017	24	30		LLL 24,000 LBS						1		1											TH 25			
							SHEET TOTALS	33.50	0.00	4	1	2	5	10	1	3		~~45~~											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
												3	6					54.50											
							TOWN TOTALS	500.47	0.00	53	12	14	117	67	60	69		1035											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**

FILE NAME: **z16T042 VT104-FAIRFAX NB.xl** PLOT DATE: **3/10/2017**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
FAIRFAX VT104 NB 9 SHEET **85** OF **146**