DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
FAIRFAX			**VT104**	**SB**			FYG-FLUORESCENT YELLOW-GREEN																				"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
	13.363	E	W1-8R	18	24		CHEVRON						1														BACK TO BACK			
		F	W1-8L	18	24			3.00																				X		
SB	13.362	E	W1-8R	18	24			3.00								1		13.25 X									INSTALL SIGN 5 FEET FROM EXISTING SIGN ASSEMBLY	X		
SB	13.348	F	W1-8L	18	24		CHEVRON			1				1													BACK TO BACK			
		E	W1-8R	18	24		CHEVRON			1																	BACK TO BACK			
SB	13.343	G	VR-017	24	30		LLL 24,000 LBS			1				1													TH 3			
SB	13.333	H	R1-1	30	30		STOP						1		1												TH 3			
		F	VD3-1	42	12		LOOMIS RD OAKLAND STA.	3.50 3.50					1 1			1		12.25 X								WRONG ROAD NAME IN PLANS, ONE SIGN TAKEN DOWN BY TOWN, REPLACED WITH OAKLAND STATION RD	TH 3		10
		H	R1-1	30	30			6.00 6.25					1 1														TH 3	X		
SB	13.283	F	R2-1	24	30		SPEED LIMIT 50						1		1															
		F	R2-1	24	30			5.00								1		13.25 X										X		
SB	12.868	F	W2-2R	30	30		RIGHT SIDE ROAD						1	1																
		F	W2-2R	30	30			6.25																				X		
SB	12.803	F	W11-2	30	30		PEDESTRIAN						1		1												SYMBOL			
		F	W7-3aP	24	18		NEXT 1/2 MILE						1																	
SIGN SUMMARY SHEET							SHEET TOTALS	27.00	0.00	3	0	0	~~6~~	3	3	3		~~45~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION								36.50					8					38.75										
							TOWN TOTALS	636.46	0.00	50	13	11	134	62	79	92		1380										

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**
FILE NAME: **z16T042 VT104-FAIRFAX SB.xl** PLOT DATE: **3/10/2017**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
FAIRFAX VT104 SB 2 SHEET **97** OF **146**