DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
FAIRFAX			**VT104**	**SB**			FYG-FLUORESCENT YELLOW-GREEN																			"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	6.185	F	VD-018A	30	18		FAIRFAX						1		1											CAMBRIDGE 8			
		F	VD-701	6	10		BRIDGE 10A VT 104				1	1	1			2		12.50 X 13.00								SALVAGE SIGN ON NEW POST IN EXISTING LOCATION			
		F	VD-018A	36	24			6.00																				
SB	6.133	F	W3-5	36	36		SPEED REDUCTION SL 30					1	1		2														
SB	6.088	F	R2-1	24	30		SPEED LIMIT 30				1	1	1		1											SALVAGE SIGN TO NB MM 5.598			
SB	5.993	F	VD-062B	72	16		BUCK HOLLOW FARM <===			1				2												B&B ANTIQUES 6			
SB	5.973	F	VD3-1	30	12		PAIGE RD			1				1															
		H	R1-1	30	30		STOP			1																			
SB	5.903	F	VD3-1	36	6		SUMMIT VIEW ST PVT			1				1															
SB	5.852	F	W3-5	36	36			9.00			1		1			2		16.00 X 15.50			MOVED TO SB 6.133						INSTALL SIGN 75 FEET NORTH FROM EXISTING "SPEED LIMIT 30" SIGN	X		
SB	5.838	F	R2-1	24	30		SPEED LIMIT 30				1		1		1											SALVAGE SIGN TO NB MM 5.177			
SB	5.758	F	W11-8	30	30		FIRE ENGINE						1		1											SYMBOL			
		F	W11-8	30	30			6.25								1		14.50 X									X		
SB	5.748	F	R2-1	30	36			7.50			1		1			1		14.25 X			MOVED TO SB 6.088						INSTALL SIGN 50 FEET NORTH OF EXISTING SPEED LIMIT 30 SIGN	X		
SB	5.738	F	R2-1	24	30		SPEED LIMIT 30						1		1														
							SHEET TOTALS	28.75	0.00	4	3	1	7	4	7	6		~~90~~											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
																		85.75											
							TOWN TOTALS	636.46	0.00	50	13	11	134	62	79	92		1380											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**

FILE NAME: **z16T042 VT104-FAIRFAX SB.xl** PLOT DATE: **3/10/2017**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
FAIRFAX VT104 SB 10 SHEET **105** OF **146**