DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
FAIRFAX			**VT104**	**SB**			FYG-FLUORESCENT YELLOW-GREEN																			"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	4.208	G	VR-017	24	30		LLL 24,000 LBS						1		1											TH 44			
		G	VR-017	24	30			5.00								1	14.50 X								TH 44			T-70
SB	4.198	F	VD3-1	36	9		SAND HILL RD						1		1											TH 44			
SB	4.197	H	R1-1	30	30		STOP						1		1											TH 44			
		G	VD-700	6	10		MM 0104, 0604, 0427				1	1	1			2		30.50 X								TH 44. SALVAGE SIGN ON NEW POST IN EXISTING LOCATION			
		F	VD3-1	60	12			5.00																		TH 44		10	
		H	R1-1	30	30			6.25																		TH 44	X		
SB	4.133	F	R2-1	24	30		SPEED LIMIT 40						1		1														
		G	VD-700	6	10		MM 0104, 0604, 0420				1	1	1			1		12.75 X								SALVAGE SIGN ON NEW POST IN EXISTING LOCATION			
		F	R2-1	24	30			5.00																		REQUIRES VEGETATION CLEARING	X		
SB	4.068	F	VW-054R	30	30			6.25								1	14.00 X								INSTALL PROPOSED SIGN 345 FEET SOUTH FROM EXISTING "SPEED LIMIT 40" SIGN			T-80
SB	3.943	F	R2-1	24	30		SPEED LIMIT 50						1		1														
SB	3.933	F	R2-1	24	30			5.00								1	13.50 X								INSTALL SIGN 50 FEET SOUTH OF EXISTING SIGN	X		
SB	3.583	F	VD-062B	72	16		RIVER BERRY FARM <---			1				2												CROSS BRIDGE, THEN LEFT 1			
SB	3.273	G	VR-017	24	30		LLL 24,000 LBS						1	1												TH 45			
							SHEET TOTALS	32.50	0.00	1	2	2	8	3	5	6		~~90~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
																		85.25										
							TOWN TOTALS	636.46	0.00	50	13	11	134	62	79	92		1380										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**

FILE NAME: **z16T042 VT104-FAIRFAX SB.xl** PLOT DATE: **3/10/2017**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
FAIRFAX VT104 SB 18 SHEET **113** OF **146**