DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ST ALBANS TOWN			**VT104**	**NB**			FYG-FLUORESCENT YELLOW-GREEN																			"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
NB	2.422	A	VW-619	30	30		SHOULDER NARROWS						1		1														
		A	VW-619	36	36			9.00								2		13.00 X 13.50										T-82
NB	2.527	A	R2-1	24	30		SPEED LIMIT 40						1	1												THIN & TRIM			
		A	R2-1	24	30			5.00																		X		
NB	2.732	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		1														
NB	2.767	A	W1-4R	30	30			6.25								1		13.50 X								INSTALL SIGN 185 FEET NORTH OF EXISTING LOCATION	X		
NB	2.827	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		1														
		A	VD-700	6	10		MM 0104, 0613, 0280				1	1	1			1	7.75 X									SALVAGE SIGN ON NEW POST			
NB	2.942	A	M3-1	24	12		NORTH						1		1														
		A	VM1-5	30	24		VT 104						1																
		A	M3-1	24	12			2.00								1		13.25 X								GREEN ON WHITE	X		
		A	VM1-5	30	24			5.00																				E-136B
NB	2.997	A	VD3-1	42	12		FRENCH HILL RD			1				1													TH 14			
		A	VD3-1	42	12		FISHER POND RD			1																	TH 14			
NB	3.002	G	VR-017	24	30		LLL 24,000 LBS			1				1													TH 14			
							SHEET TOTALS	27.25 SF	0.00 SF	3 EA	1 EA	1 EA	7 EA	3 EA	4 EA	5 EA		~~75~~ FT		0	0								
							TOWN TOTALS	327.93	0.00	62	3	3	80	40	33	40		61.00 600		2	247								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**

FILE NAME: **z16T042 VT104-ST ALBANS NI** PLOT DATE: **3/10/2017**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
ST ALBANS TOWN VT104 NB 12 SHEET **131** OF **146**