DIR	MILEPOINT	LOCATION CODE	MUTCD CODE	WIDTH	HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (in) 1.75 (LB / FT) 1.88	SQUARE STEEL (in) 2.00 (LB / FT) 2.42	SQUARE STEEL (in) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ST ALBANS TOWN			**VT104**	**SB**			FYG-FLUORESCENT YELLOW-GREEN																				"SHSM" - STANDARD HIGHWAY SIGNS AND MARKINGS			
SB	4.032	F	R2-1	24	30		SPEED LIMIT 40						1		1														
		F	R2-1	24	30			5.00								1		14.25 X									X		
SB	3.207	F	W1-4R	30	30		RIGHT REVERSE CURVE						1		1														
SB	3.182	F	W1-4R	30	30			6.25								1		15.75 X								INSTALL SIGN 130 FEET SOUTH OF EXISTING LOCATION. REQUIRES VEGETATION CLEARING	X		
SB	3.162	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		1														
SB	3.067	F	R2-1	24	30			5.00								1		15.00 X								INSTALL SIGN ACROSS ROAD FROM EXISTING SL40 SIGN	X		
SB	2.837	E	W1-6R	48	24		RIGHT --->						1		1												LARGE ARROW			
		E	W1-6R	48	24			8.00								2		13.00 X 13.00									X		
SB	2.817	F	VD3-1	36	12		CONGRESS ST			1				1												TH 8			
		F	VD3-1	42	12		FISHER POND RD			1																TH 8			
SB	2.815	G	VR-017	24	30		LLL 24,000 LBS			1				1												TH 8			
SB	2.807	H	R1-1	30	30		STOP			1				1												TH 8			
		G	VD-700	6	10		MM 0104, 0613, 0277			1																TH 8			
SB	2.777	F	R2-1	24	30		SPEED LIMIT 40						1		1														
		F	R2-1	24	30			5.00								1		14.50 X									X		
SIGN SUMMARY SHEET							SHEET TOTALS	29.25	0.00	5	0	0	5	3	5	6		~~90~~		0	0								
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
VERMONT AGENCY OF TRANSPORTATION																		85.50											
							TOWN TOTALS	227.21	0.00	47	4	4	62	36	26	27		405		4	605								

PROJECT NAME: **STATEWIDE- NORTHWEST**
PROJECT NUMBER: **STPG SIGN (58)**

FILE NAME: **z16T042 VT104-ST ALBANS SI** PLOT DATE: **3/10/2017**
PROJECT MANAGER: **B. BRESLEND** DRAWN BY: **O. DALMER**
DESIGNED BY: **O. DALMER** CHECKED BY: **B. BRESLEND**
ST ALBANS TOWN VT104 SB 2 SHEET **136** OF **146**