

TOWN TOTAL SIGN SUMMARY SHEET

STATEWIDE-NORTHWEST STPG SIGN(58)

Town Name - Route	County	Town Mileage	NEW SIGNS (SF)		EXISTING SIGNS (EA)				EXIST POST (EA)		SQUARE STEEL (IN)			TOTAL POSTS	SQUARE TUBE SIGN POST AND ANCHOR (LF)	FOUNDATION	TUBULAR STEEL Ø (IN)					
			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE	1.75	2.00	2.50				(LB / FT)					
											1.88	2.42	3.35				3.00	3.50	4.00	5.00		
ST ALBANS VT36 EB	FRANKLIN	5.217	354.00	326.25	0.00	76	7	7 12	62 71	52	29	0	40	5	45	622.50	1	131.10	210	0	0	0
ST ALBANS VT36 WB	FRANKLIN	5.217	356.70	330.90	0.00	63	6	6 13	66 82	56	29	0	33	6	39	560.80	2	264.10	420	0	0	0
FAIRFIELD VT36 EB	FRANKLIN	9.989	486.30	461.50	0.00	25	16	16 18	87 90	32	60	0	83	9	92	1219.80	0	0	0	0	0	
FAIRFIELD VT36 WB	FRANKLIN	9.989	357.80	351.58	0.00	16	7	5 6	55 57	24	35	0	56	8	64	879.80	0	0	0	0	0	
BAKERSFIELD VT36 EB	FRANKLIN	2.507	85.50	79.50	0.00	4	1	3	14 16	4	11	0	18	0	18	261.80	0	0	0	0	0	
BAKERSFIELD VT36 WB	FRANKLIN	2.507		82.00	0.00	3	1	1	21	5	13	0	16	0	16	204.00	0	0	0	0	0	
				1722.23				53	337									395.20				
Total		17.713		1631.73	0.00	187	38	38	305	173	177	0	246	28	274	3748.50	3	630	0	0	0	
CAMBRIDGE VT 104 NB	LAMOILLE	1.967		51.25	0.00	5	1	1	10 9	5	9	0	10	0	10	95.80	0	0	0	0	0	
CAMBRIDGE VT 104 SB	LAMOILLE	1.967	105.20	89.19	0.00	12	1	1 0	17 16	11	11	0	12	2	14	143.30	0	0	0	0	0	
FAIRFAX VT104 NB	FRANKLIN	14.185	523.20	500.47	0.00	53	12	14 20	117 127	67	60	0	57	12	69	1045.00	0	0	0	0	0	
FAIRFAX VT104 SB	FRANKLIN	14.185	658.50	636.46	0.00	50	13	11 26	134 151	62	79	1	75	16	92	1376.30	0	0	0	0	0	
GEORGIA VT104 NB	FRANKLIN	0.130		5.84	0.00	0	0	0 3	0 3	0	0	0	2	0	2	26.00	0	0	0	0	0	
FAIRFIELD VT104 NB	FRANKLIN	0.111		5.84	0.00	0	0	0	0	0	0	0	2	0	2	24.50	0	0	0	0	0	
ST ALBANS VT104 NB	FRANKLIN	4.110		327.93	0.00	62	3	3 2	80 79	40	33	1	26	13	40	527.50	2	161.50	247	0	0	0
ST ALBANS VT104 SB	FRANKLIN	4.110	245.20	227.21	0.00	47	4	4 6	62 67	36	26	0	23	4	27	370.00	4	459.80	605	0	0	0
				1922.90				58	452									621.30				
Total		20.503		1844.19	0.00	229	34	34	420	221	218	2	207	47	256	3608.3	6	852	0	0	0	
				3645.10				111	789									1017.00				
	SUBTOTAL	38.216		3475.92	0.00	416	72	72	725	394	395	2	453	75	530	7357.00	9	1482	0	0	0	
	ROUNDING	--		4.08	--	--	--	--	--	--	--	--	--	--	--		--	18	--	--	--	
	PROJECT TOTAL	38.216		3480.00	0.00	416	72	72	725	394	395	2	453	75	530	7357.00	9	1500	0	0	0	
								111	789									1017.00				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME:	STATEWIDE-NORTHWEST
PROJECT NUMBER:	STPG SIGN (58)
FILE NAME:	z16T042towntotal.dgn
PROJECT LEADER:	B. BRESLEND
DESIGNED BY:	O. DALMER
TOWN TOTAL SIGN SUMMARY SHEET	
PLOT DATE:	3/10/2017
DRAWN BY:	O. DALMER
CHECKED BY:	C. LATHROP
SHEET	146 OF 146