

COMPOSITE QUANTITY SHEET 1

ST. ALBANS TOWN STP FPAV(1)					ST. ALBANS TOWN STP FPAV(2)					TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES				
FEDERAL NON- PARTICIP.	ROADWAY	BRIDGE	FULL C.E. ITEMS	ROADWAY (ALTERNATE A)	ROADWAY (ALTERNATE B)	FEDERAL NON- PARTICIP.	ROADWAY	BRIDGE	FULL C.E. ITEMS	ROADWAY (ALTERNATE A)	ROADWAY (ALTERNATE B)	ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
	150						100						250		CY	EARTH BORROW	203.30			
	1						1						2		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22			
	1100						1460						2560		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10			
	300						300						600		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28			
																BEGIN OPTION AA				
	670						420						1090		CWT	EMULSIFIED ASPHALT (RS-1)	404.65			
	670						420						1090		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683			
																END OPTION AA				
	1						1						2		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I)	406.50			
	6												6		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412			
	20						30						50		HR	POWER GRADER RENTAL	608.15			
	75						85						160		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25			
	20						30						50		HR	POWER BROOM RENTAL, TYPE I	608.30			
	40						50						90		HR	POWER BROOM RENTAL, TYPE II	608.31			
	150						170						320		HR	TRUCK RENTAL	608.37			
	20						20						40		HR	LOADER RENTAL, TYPE I	608.40			
	250						175						425		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20			
	6						4						10		EACH	ANCHOR FOR STEEL BEAM RAIL	621.6			
							1						1		EACH	REPLACE GUARDRAIL BEAM UNIT	621.77			
	679												679		LF	ADJUST HEIGHT OF GUARDRAIL	621.79			
	225						150						375		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80			
	500						500						1000		HR	UNIFORMED TRAFFIC OFFICERS	630.10			
	1500						1700						3200		HR	FLAGGERS	630.15			
							50						50		HR	FLAGGERS, RAILROAD	630.20			
			0.5										1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17			
	0.5						0.5						1		LS	MOBILIZATION/DEMOBILIZATION	635.11			
	1												1		EACH	TRAFFIC CONTROL (STP FPAV(1))	641.10			
							1						1		EACH	TRAFFIC CONTROL (STP FPAV (2))	641.10			
	2						2						4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15			
	30500						36000						66500		LF	4 INCH WHITE LINE, WATERBORNE PAINT	646.201			
	31000						33000						64000		LF	4 INCH YELLOW LINE, WATERBORNE PAINT	646.2111			
	90												90		LF	8 INCH YELLOW LINE, WATERBORNE PAINT	646.231			
	30												30		LF	24 INCH STOP BAR, WATERBORNE PAINT	646.261			
	14												14		EA	LETTER OR SYMBOL, WATERBORNE PAINT	646.301			
							2						2		EA	RAILROAD CROSSING SYMBOL, WATERBORNE PAINT	646.321			
	30500						36000						66500		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602			
	31000						33000						64000		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612			
	90												90		LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652			
	30												30		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682			
	14												14		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692			

PROJECT NAME: ST ALBANS TOWN
PROJECT NUMBER: STP FPAV(1)/STP FPAV(2)
FILE NAME: z16v020-composite.dgn PLOT DATE: 05/10/2016
PROJECT LEADER: C. LATHROP DRAWN BY: J. GOODALL
DESIGNED BY: J. GOODALL CHECKED BY: C. LATHROP
COMPOSITE QUANTITY SHEET 1 SHEET 4 OF 32