

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	FULL C.E.	ROADWAY (ALTERNATE A)	ROADWAY (ALTERNATE B)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							150				150		CY	EARTH BORROW	203.30	-			
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
							1100				1100		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	13			
							300				300		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	EST.			
														BEGIN OPTION AA					
							670				670		CWT	EMULSIFIED ASPHALT (RS-1)	404.65	10			
							670				670		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	10			
														END OPTION AA					
							1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
							6				6		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			
							20				20		HR	POWER GRADER RENTAL	608.15	EST.			
							75				75		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
							20				20		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
							40				40		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
							150				150		HR	TRUCK RENTAL	608.37	EST.			
							20				20		HR	LOADER RENTAL, TYPE I	608.40	EST.			
							250				250		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	13			
							6				6		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
							679				679		LF	ADJUST HEIGHT OF GUARDRAIL	621.79	-			
							225				225		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
							500				500		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							1500				1500		HR	FLAGGERS	630.15	EST.			
								0.5			0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
							0.5				0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1				1		LS	TRAFFIC CONTROL (STP FPAV(1))	641.10	-			
							2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
							30500				30500		LF	4 INCH WHITE LINE, WATERBORNE PAINT	646.201	315			
							31000				31000		LF	4 INCH YELLOW LINE, WATERBORNE PAINT	646.2111	764			
							90				90		LF	8 INCH YELLOW LINE, WATERBORNE PAINT	646.231	10			
							30				30		LF	24 INCH STOP BAR, WATERBORNE PAINT	646.261	-			
							14				14		EACH	LETTER OR SYMBOL, WATERBORNE PAINT	646.301	-			
							30500				30500		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	315			
							31000				31000		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	764			
							90				90		LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	10			
							30				30		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	-			
							14				14		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
							6200				6200		EACH	LINE STRIPING TARGETS	646.76	148			
							15				15		LB	SEED	651.15	-			
							25				25		LB	FERTILIZER	651.18	-			
							1				1		TON	AGRICULTURAL LIMESTONE	651.20	0.91			

PROJECT NAME: ST ALBANS TOWN  
PROJECT NUMBER: STP FPAV(I)  
FILE NAME: z16v020qnty.dgn PLOT DATE: 05/10/2016  
PROJECT LEADER: C. LATHROP DRAWN BY: J. GOODALL  
DESIGNED BY: J. GOODALL CHECKED BY: C. LATHROP  
QUANTITY SHEET 1 SHEET 13 OF 32