

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	BRIDGE	FULL C.E.	ROADWAY (ALTERNATE ZA1)	ROADWAY (ALTERNATE ZA2)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						6175					6175		LF	SHOULDER BERM REMOVAL	203.40	EST.			COLD PLANING, BITUMINOUS PAVEMENT
						1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	361 SY		BEGIN PROJECT
						2075					2075		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	27	375 SY		BRIDGE 57 APPROACH
						300					300		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	EST.	388 SY		BRIDGE 57 & BRIDGE 58
														BEGIN OPTION AA			375 SY		BRIDGE 58 APPROACH
						520					520		CWT	EMULSIFIED ASPHALT	404.65	1	549 SY		END PROJECT
						520					520		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	1			
														END OPTION AA					
						1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-	2048 SY		SUBTOTAL
							55				55		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	3	27 SY		ROUNDING
							50				50		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.	2075 SY		TOTAL
						35					35		HR	POWER GRADER RENTAL	608.15	EST.			
						105					105		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
						25					25		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
						45					45		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			
						210					210		HR	TRUCK RENTAL	608.37	EST.			
						15					15		HR	LOADER RENTAL, TYPE I	608.40	EST.			
						550					550		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	17.5			
						270					270		EACH	STEEL BEAM GUARDRAIL DELINEATOR	621.218	EST.			
						12					12		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
						2100					2100		LF	REMOVE AND RESET GUARDRAIL	621.75	25			
						525					525		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	12.5			
						320					320		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
						1280					1280		HR	FLAGGERS	630.15	EST.			
								1			1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
						1					1		LS	TRAFFIC CONTROL	641.10	-			
						3					3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
						34000					34000		LF	4 INCH WHITE LINE, WATERBORNE PAINT	646.201	344			
						35100					35100		LF	4 INCH YELLOW LINE, WATERBORNE PAINT	646.2111	370			
						640					640		LF	8 INCH YELLOW LINE, WATERBORNE PAINT	646.231	14			
						15					15		EACH	LETTER OR SYMBOL, WATERBORNE PAINT	646.301	-			
						34000					34000		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	344			
						35100					35100		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	370			
						15					15		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
						6850					6850		EACH	LINE STRIPING TARGETS	646.76	83			
						24					24		EACH	DELINEATOR WITH STEEL POST	676.10	EST.			
						24					24		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	EST.			
						1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
						600					600		SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	2			

PROJECT NAME: ROXBURY-NORTHFIELD
PROJECT NUMBER: STP FPAV(6)
FILE NAME: z16v027frm.dgn PLOT DATE: 2/8/2017
PROJECT LEADER: P. SHEDD DRAWN BY: S. GOODWIN
DESIGNED BY: N. LEMAY CHECKED BY: P. SHEDD
QUANTITY SHEET 1 SHEET 7 OF 21