STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	BRIDGE	FULL C.E.	ROADWAY (ALTERNATE ZA1)	ROADWAY (ALTERNATE ZA2)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND
1200					1200		TON	SPECIAL PROVISION (AGGREGATE SHOULDERS, RAP WITH RAS)	900.680	21
50					50		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST.
								BEGIN ALTERNATE ZA1		
			6830		6830		TON	MEDIUM DUTY BITUMINOUS CONCRETE PAVEMENT	406.27	10
			1		1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	406.28	-
								END ALTERNATE ZA1		
								BEGIN ALTERNATE ZA2		
				6830	6830		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	10
				1	1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
								END ALTERNATE ZA2		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE ZA1
4556	TON	TYPE IV, WEARING COURSE
2264	TON	TYPE IV, LEVELING COURSE
6820	TON	SUBTOTAL
10	TON	ROUNDING
6830	TON	TOTAL
		ALTERNATE ZA2
4556	TON	TYPE IVS, WEARING COURSE
2264	TON	TYPE IVS, LEVELING COURSE
6820	TON	SUBTOTAL
10	TON	ROUNDING
6830	TON	TOTAL

PROJECT NAME: ROXBURY-NORTHFIELD
PROJECT NUMBER: STP FPAV(6)

FILE NAME: z16v027frm.dgn
PROJECT LEADER: P. SHEDD
DESIGNED BY: N. LEMAY
QUANTITY SHEET 2

PLOT DATE: 2/8/2017
DRAWN BY: S. GOODWIN
CHECKED BY: P. SHEDD
SHEET 8 OF 21