

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
								ROADWAY	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								75			75		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	5			SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)
								34			34		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-	478.446 SY	MAINLINE	
								45750			45750		EACH	LINE STRIPING TARGETS	646.76	EST	40.916 SY	BRIDGES	
								75			75		LB	SEED	651.15	EST	29.693 SY	EXIT 8 RAMPS	
								75			75		LB	FERTILIZER	651.18	EST	15.068 SY	EXIT 9 RAMPS	
								0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20	EST	2277 SY	ROUNDING	
								0.5			0.5		TON	HAY MULCH	651.25	EST	586.400 SY	TOTAL	
								100			100		CY	TOPSOIL	651.35	EST			SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)(PG 70-28)(SBS POLYMER)(3/4" LT+/-1/8")
								80			80		SY	TEMPORARY EROSION MATTING	653.20	EST	478.446 SY	MAINLINE	
								158			158		EACH	DELINEATOR WITH STEEL POST	676.10	-	40.916 SY	BRIDGES	
								158			158		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-	29.693 SY	EXIT 8 RAMPS	
								3535			3535		EACH	REMOVE AND REPLACE REFLECTOR UNIT	676.15	EST	15.068 SY	EXIT 9 RAMPS	
								1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-	2277 SY	ROUNDING	
														BEGIN OPTION BB			586.400 SY	TOTAL	
								34			34		EACH	SPECIAL PROVISION (DURABLE LETTER OR SYMBOL, EPOXY)(28 MILS)	900.620	-			
								34			34		EACH	SPECIAL PROVISION (DURABLE LETTER OR SYMBOL, POLYUREA)(28 MILS)	900.620	-			
														END OPTION BB					
								25			25		LF	SPECIAL PROVISION (ALUMINUM APPROACH RAILING)	900.640	-			
														BEGIN OPTION CC					
								4000			4000		LF	SPECIAL PROVISION (DURABLE 12 INCH WHITE LINE, EPOXY)(28 MILS)	900.640	105			
								4000			4000		LF	SPECIAL PROVISION (DURABLE 12 INCH WHITE LINE, POLYUREA)(28 MILS)	900.640	105			
														END OPTION CC					
														BEGIN OPTION DD					
								75			75		LF	SPECIAL PROVISION (DURABLE 24 INCH STOP BAR, EPOXY)(28 MILS)	900.640	EST			
								75			75		LF	SPECIAL PROVISION (DURABLE 24 INCH STOP BAR, POLYUREA)(28 MILS)	900.640	EST			
														END OPTION DD					
														BEGIN OPTION EE					
								240800			240800		LF	SPECIAL PROVISION (DURABLE 6 INCH WHITE LINE, EPOXY)(28 MILS)	900.640	293			
								240800			240800		LF	SPECIAL PROVISION (DURABLE 6 INCH WHITE LINE, POLYUREA)(28 MILS)	900.640	293			
														END OPTION EE					
														BEGIN OPTION FF					
								122400			122400		LF	SPECIAL PROVISION (DURABLE 6 INCH YELLOW LINE, EPOXY)(28 MILS)	900.640	304			
								122400			122400		LF	SPECIAL PROVISION (DURABLE 6 INCH YELLOW LINE, POLYUREA)(28 MILS)	900.640	304			
														END OPTION FF					
									700		700		SF	SPECIAL PROVISION (ASPHALTIC APPROACH MATERIAL)	900.670	12			
								566400			566400		SY	SPECIAL PROVISION (MICRO-MILLING BITUMINOUS CONCRETE PAVEMENT)	900.675	2277			
								566400			566400		SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)(PG 70-28)(SBS POLYMER)(3/4" LT+/-1/8")	900.675	2277			
								150			150		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST			

PROJECT NAME: MONTPELIER-WATERBURY
 PROJECT NUMBER: IM SURF(59)
 FILE NAME: pl6v098 Montpelier-Water.dgn PLOT DATE: 20-MAR-2018
 PROJECT LEADER: M. BOGACZYK DRAWN BY: N. PAPPAS
 DESIGNED BY: N. PAPPAS CHECKED BY: M. BOGACZYK
 QUANTITY SHEET 2 SHEET 10 OF 34